FED. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2509	08-00094-02-BT	KANE	33	3
STA.	TO STA.			
EXISTING CONDITIONS:				

CONTRACT #63125

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE Y046 CMAO/KDOT 80/20		
	20200100	EARTH EXCAVATION	CU YD	1320	1320		
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	204	204		
	20800150	TRENCH BACKFILL	CU YD	21	21		
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4488	4488		
	25000110	SEEDING, CLASS 1A	ACRE	0.93	0.93		
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	93	93		
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	93	93		
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	93	93		
	25100630	EROSION CONTROL BLANKET	SQ YD	4488	4488		
	28000400	PERIMETER EROSION BARRIER	FOOT	3850	3850		
	35101800	AGGREGATE BASE COURSE, TYPE B, 6"	SQ YD	2858	2858		
	40603310	HOT MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	378	378		
	40603340	HOT MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	0.2	0.2		
	42400800	DETECTABLE WARNINGS	SQ FT	160	160		
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	394	394		
	44000600	SIDEWALK REMOVAL	SQ FT	2222	2222		
	550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	119	119		
	60202705	CATCH BASINS, TYPE A, 4'-DIAMETER WITH SALVAGED FRAME AND GRATE	EACH	1	1		
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1		
	60500060	REMOVING INLETS	EACH	1	1		
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	394	394		
	67100100	MOBILIZATION	L SUM	1	1		
	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1		
●	78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	376	376		
●	78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	550	550		
●	81400115	HANDHOLE TO BE ADJUSTED	EACH	1	1		
●	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	FOOT	2	2		
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	613	613		
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	613	613		
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	12	12		
*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	11	11		
●	89502200	MODIFY EXISTING CONTROLLER	EACH	1	1		
●	X0325890	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1	1		

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE Y046 CMAO/KDOT 80/20		
●	X8950307	REMOVE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	8	8		
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
	44201364	CLASS C PATCHES, TYPE I, 11 3/4"	SQ YD	1.4	1.4		
	XX000613	MODULAR BLOCK RETAINING WALL	SQ FT	1000	1000		
●	XX008197	REMOVE EXISTING PEDESTRIAN PUSH BUTTON	EACH	3	3		

● DENOTES A SPECIALTY ITEM

PLOT DATE: $$DATE$$

...\Plans\SOQ01.dgn 8/18/2009 3:25:00 PM