

## SUMMARY OF QUANTITIES

|                       |                                                                           |        |                | STP                                                      |                                                   |                                                        | ROADWAY RESURFACING                          |
|-----------------------|---------------------------------------------------------------------------|--------|----------------|----------------------------------------------------------|---------------------------------------------------|--------------------------------------------------------|----------------------------------------------|
|                       |                                                                           |        |                | RDWY. WIDENING<br>F.A.P. 662<br>80% FEDERAL<br>20% STATE | ROADWAY<br>F.A.P. 662<br>80% FEDERAL<br>20% STATE | STRUCTURE<br>S.N. 059-7004<br>80% FEDERAL<br>20% STATE | PARKING<br>LANES<br>50% STATE<br>50% VILLAGE |
| SUMMARY OF QUANTITIES |                                                                           |        |                | CONSTRUCTION TYPE CODE                                   |                                                   |                                                        | CONSTRUCTION TYPE CODE                       |
| CODE NO.              | PAY ITEM                                                                  | UNIT   | TOTAL QUANTITY | 1000-2A                                                  | 1000-2A                                           | X028-2A                                                | Y025                                         |
| 60264100              | INLETS TO BE RECONSTRUCTED WITH NEW TYPE 15 FRAME AND LID                 | EACH   | 2              |                                                          | 2                                                 |                                                        |                                              |
| 60605000              | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24                         | FOOT   | 99             | 91                                                       | 8                                                 |                                                        |                                              |
| 63100167              | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT                        | EACH   | 2              |                                                          | 2                                                 |                                                        |                                              |
| 63200310              | GUARDRAIL REMOVAL                                                         | FOOT   | 137.5          |                                                          | 137.5                                             |                                                        |                                              |
| 64200105              | SHOULDER RUMBLE STRIP                                                     | FOOT   | 27772          | 1170                                                     | 26602                                             |                                                        |                                              |
| 66600105              | FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS                              | EACH   | 10             |                                                          | 10                                                |                                                        |                                              |
| 67000400              | ENGINEER'S FIELD OFFICE, TYPE A                                           | CAL MO | 12             |                                                          | 12                                                |                                                        |                                              |
| 67100100              | MOBILIZATION                                                              | L SUM  | 1              | 0.5                                                      | 0.5                                               |                                                        |                                              |
| 70100405              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321                           | EACH   | 1              |                                                          | 1                                                 |                                                        |                                              |
| 70100450              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201                           | L SUM  | 1              | 0.5                                                      | 0.5                                               |                                                        |                                              |
| 70100460              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306                           | L SUM  | 1              | 0.5                                                      | 0.5                                               |                                                        |                                              |
| 70100500              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326                           | L SUM  | 1              | 0.5                                                      | 0.5                                               |                                                        |                                              |
| 70101830              | TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21                           | L SUM  | 1              |                                                          | 1                                                 |                                                        |                                              |
| 70102620              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501                           | L SUM  | 1              | 0.5                                                      | 0.5                                               |                                                        |                                              |
| 70102635              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701                           | L SUM  | 1              | 0.5                                                      | 0.5                                               |                                                        |                                              |
| 70103815              | TRAFFIC CONTROL SURVEILLANCE                                              | CAL DA | 20             | 20                                                       |                                                   |                                                        |                                              |
| 70106500              | TEMPORARY BRIDGE TRAFFIC SIGNALS                                          | EACH   | 1              |                                                          | 1                                                 |                                                        |                                              |
| 70106800              | CHANGEABLE MESSAGE SIGN                                                   | CAL MO | 4              | 2                                                        | 2                                                 |                                                        |                                              |
| 70300100              | SHORT-TERM PAVEMENT MARKING                                               | FOOT   | 3808           | 392                                                      | 3416                                              |                                                        |                                              |
| 70300210              | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS                          | SQ FT  | 404            | 281                                                      | 123                                               |                                                        |                                              |
| 70300230              | TEMPORARY PAVEMENT MARKING - LINE 5"                                      | FOOT   | 62328          | 9194                                                     | 53134                                             |                                                        |                                              |
| 70300250              | TEMPORARY PAVEMENT MARKING - LINE 8"                                      | FOOT   | 78             | 78                                                       |                                                   |                                                        |                                              |
| 70300280              | TEMPORARY PAVEMENT MARKING - LINE 24"                                     | FOOT   | 84             | 18                                                       | 66                                                |                                                        |                                              |
| 70301000              | WORK ZONE PAVEMENT MARKING REMOVAL                                        | SQ FT  | 28181          | 4363                                                     | 23818                                             |                                                        |                                              |
| 70400100              | TEMPORARY CONCRETE BARRIER                                                | FOOT   | 850            |                                                          | 850                                               |                                                        |                                              |
| 70400200              | RELOCATE TEMPORARY CONCRETE BARRIER                                       | FOOT   | 850            |                                                          | 850                                               |                                                        |                                              |
| 70500100              | TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A                             | FOOT   | 25             |                                                          | 25                                                |                                                        |                                              |
| 70500500              | TEMPORARY STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES             | FOOT   | 12.5           |                                                          | 12.5                                              |                                                        |                                              |
| 78000300              | THERMOPLASTIC PAVEMENT MARKING - LINE 5"                                  | FOOT   | 16729          | 9174                                                     | 7555                                              |                                                        |                                              |
| 78000500              | THERMOPLASTIC PAVEMENT MARKING - LINE 8"                                  | FOOT   | 78             | 78                                                       |                                                   |                                                        |                                              |
| 78000650              | THERMOPLASTIC PAVEMENT MARKING - LINE 24"                                 | FOOT   | 18             | 18                                                       |                                                   |                                                        |                                              |
| 78004200              | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS | SQ FT  | 404            | 281                                                      | 123                                               |                                                        |                                              |
| 78004220              | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"             | FOOT   | 4300           | 20                                                       | 4280                                              |                                                        |                                              |
| 78004280              | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"            | FOOT   | 66             |                                                          | 66                                                |                                                        |                                              |
| 78100100              | RAISED REFLECTIVE PAVEMENT MARKER                                         | EACH   | 364            | 108                                                      | 256                                               |                                                        |                                              |
| 78200455              | BIDIRECTIONAL GUARD RAIL REFLECTORS                                       | EACH   | 2              |                                                          | 2                                                 |                                                        |                                              |

### \*Specialty Items

Rev.

|                                           |                                            |             |           |                                                                                       |                                                                                                                                                     |                         |  |  |  |                         |         |                    |                     |                           |  |  |
|-------------------------------------------|--------------------------------------------|-------------|-----------|---------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|--|--|--|-------------------------|---------|--------------------|---------------------|---------------------------|--|--|
| FILE NAME =                               | USER NAME = madonjavj                      | DESIGNED -  | REVISED - |  | Allen Henderson & Associates, Inc.<br>Civil and Structural Engineers Springfield, IL<br>62703 Phone: (217)544-8033 IL Design Firm<br>No. 184-001907 | SUMMARY OF QUANTITIES   |  |  |  | F.A.P. RTE.             | SECTION | COUNTY             | TOTAL SHEETS        | SHEET NO.                 |  |  |
| S:\PROJ ENGR 1 (Nagengard)\Dust Squad\FAP | 662 (IL 4) Henderson.pdf\CA00 Sheets\06727 | BROWN00.dgn | REVISED - |                                                                                       |                                                                                                                                                     | SCALE: NONE             |  |  |  | SHEET NO. 3 OF 4 SHEETS | STA.    | TO STA.            | FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT |  |  |
| PLOT SCALE = 2.0000' / 1 IN.              | CHECKED -                                  | REVISED -   | REVISED - |                                                                                       |                                                                                                                                                     | SHEET NO. 3 OF 4 SHEETS |  |  |  | STA.                    | TO STA. | CONTRACT NO. 72765 |                     |                           |  |  |
| PLOT DATE = Aug-17-2009 04:21:55PM        | DATE                                       | REVISED -   | REVISED - |                                                                                       |                                                                                                                                                     | SHEET NO. 3 OF 4 SHEETS |  |  |  | STA.                    | TO STA. | CONTRACT NO. 72765 |                     |                           |  |  |