

SCHEDULE PIPE CULVERT & END SECTIONS												
LOCATION	PIPE CULVERT, TY 1,RCCP 12'	STORM SEWERS, CL A TY 1 15'	PIPE CULVERT, TY 1,CS/A 15'	PIPE CULVERT, TY 1,CS/A 18'	PIPE CULVERT, TY 1,RCCP 24'	PIPE CULVERT, TY 2,CS/A 15'	PIPE CULVERT, TY 2,RCCP 42'	PIPE CULVERT, TY 1,RCCP 42'	METAL END SECTIONS 15'	PRCFES 24'	METAL END SECTIONS 18'	PRCFES 42'
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH
STA. 354+39.5 LT TO STA. 354+41.8 RT.		44										
STA. 355+62 LT.			58						2			
STA. 359+07.9 LT.			60						2			
STA. 360+00 TO STA. 361+50 RT.								146				
STA. 360+00 LT.			54						2			
STA. 361+50 RT.	10											
STA. 361+50 TO STA. 362+62 RT.								108				
STA. 363+28.9 TO STA. 364+00 RT.								68				
STA. 363+68.4 LT.			66						2			
STA. 364+00 RT.	14											
STA. 364+00 TO STA. 365+41.7 RT.								*72				1
STA. 365+14.7 LT.			50						2			
STA. 365+72.3 C							76					2
STA. 369+56.2 LT.			58						2			
STA. 442+73.5 LT.			36									
STA. 444+75.5 LT.			40									
STA. 446+27.5 LT.			36									
STA. 447+42.5 LT.						48						
STA. 447+99 RT.					62					2		
STA. 451+81 LT.				42							2	
TOTAL	24	44	458	42	62	48	76	394	12	2	2	3

SCHEDULE PAVEMENT REMOVAL	
LOCATION	QUANTITY
	SQ. YD.
STA. 354+40 LT. TO STA. 354+42 RT.	14
STA. 365+64 TO STA. 365+81	42
STA. 449+60 TO STA. 450+15 RT.	92
STA. 449+68 TO STA. 450+10 LT.	45
FROM ENTRANCE SCHEDULES	804
TOTAL	997

SCHEDULE SUB-BASE GRANULAR MATERIAL, TYPE A	
LOCATION	QUANTITY
	TON
STA. 355+00 TO STA. 370+00 LT.	1025
STA. 370+00 TO STA. 373+85 LT.	132
STA. 355+00 TO STA. 370+00 RT.	1082
STA. 370+00 TO STA. 373+85 RT.	139
STA. 448+00 TO STA. 452+50	2842
TOTAL	5220

SCHEDULE DRAINAGE STRUCTURES	* USE 66 FEET OF REMOVE AND RELAY PIPE CULVERTS, 42' TO COMPLETE.
---------------------------------	---

LOCATION	RES DEPTH MANHOLES, 7' DIAMETER, TY 8 GR	INLETS, TY A, TY 3 F&G	INLETS, TY A, MED INLET (604101)	MH TO BE ADJ W/ NEW TY 3 F&G	INLETS TO BE ADJ W/ NEW TY 1 F & CLOSED LID	INLETS TO BE RECONST W/ NEW TY 15 F & LID
	EACH	EACH	EACH	EACH	EACH	EACH
STA. 354+39.5 LT.		1				
STA. 354+41.8 RT.				1		
STA. 354+48.9 LT.					1	
STA. 354+74 LT.					1	
STA. 360+00 RT.						
STA. 361+50 RT.	1		1			
STA. 362+62 RT.						
STA. 363+28.9 RT.						
STA. 364+00 RT.	1		1			
STA. 364+74.4 RT.						
STA. 365+41 RT.						
STA. 29+99.4 RT.						1
STA. 30+38 RT.						1
TOTAL	2	1	2	1	2	2

* SCHEDULE TREE REMOVAL			
LOCATION	ACRES	6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
STA. 448+20 TO STA. 450+00 LT.	0.15		
STA. 448+25 TO STA. 448+85 RT.	0.01		
STA. 449+90 TO STA. 451+40 RT.	0.14		
STA. 449+43 RT.		9	
STA. 449+43 RT.		11	
STA. 449+43 RT.		12	
STA. 449+43 RT.		15	
STA. 449+55 RT.			17
TOTAL	0.3	47	17
* TREE REMOVAL QUANTITIES ARE SHOWN FOR ESTIMATING PURPOSES ONLY. TREE REMOVAL SHALL BE PAID FOR AS A LUMP SUM ITEM.			

SCHEDULE PIPE CULVERT REMOVAL		
LOCATION	DIAMETER	LENGTH
	INCHES	FOOT
STA. 355+62 LT.	15	52
STA. 359+08 LT.	15	52
STA. 360+00 LT.	15	52
STA. 363+68 LT.	15	55
STA. 365+15 LT	15	46
STA. 365+72.3 C	30	48
STA. 369+56 LT.	15	63
STA. 442+74 LT.	15	30
STA. 444+76 LT.	15	40
STA. 446+28 LT.	15	32
STA. 447+43 LT.	15	44
STA. 447+99 RT.	24	47
STA. 451+81 LT.	18	30
TOTAL		591

SCHEDULE TEMPORARY EROSION CONTROL ITEMS				
LOCATION	PERIMETER EROSION BARRIER	AGGREGATE (EROSION CONTROL)	TEMP. EROSION CONTROL SEEDING	INLET AND PIPE PROTECTION
	FOOT	TON	POUND	EACH
STA. 354+75 TO STA. 373+85 LT.		15	100	
STA. 354+75 TO STA. 373+85 RT.		10	90	8
STA. 444+00 TO STA. 458+00 LT.	67	25	80	
STA. 444+00 TO STA. 458+00 RT.	157	40	90	
TOTAL	224	90	360	8

SCHEDULE REMOVE AND RELAY PIPE CULVERTS 42"	
LOCATION	QUANTITY
	FOOT
STA. 364+75 TO STA. 365+41 RT	66
TOTAL	66

SCHEDULE CONCRETE COLLAR	
LOCATION	QUANTITY
	FOOT
STA. 360+00 RT.	1
STA. 362+62 RT.	1
STA. 363+28.9 RT.	1
TOTAL	3