

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000	
				80% FED STATE	20% STATE
50800515	BAR SPLICERS	EACH	285		285
51200959	FURNISHING METAL SHELL PILES 14" x 0.312"	FOOT	1867		1867
51202305	DRIVING PILES	FOOT	1867		1867
51203200	TEST PILE METAL SHELLS	EACH	2		2
51205200	TEMPORARY SHEET PILING	SQ. FT	967		967
51500100	NAME PLATES	EACH	1		1
54208665	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL, EQUIVALENT ROUND-SIZE 60"	FOOT	84	84	
54215805	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 60"	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ. YD	52		52
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	160		160
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	3100	3100	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	3340	3340	
63500105	DELINEATORS	EACH	6	6	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	25	25	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL. MO	6	6	
67100100	MOBILIZATION	L. SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L. SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L. SUM	1	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L. SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL. DA	20	20	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	493	493	
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	6184	6184	
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	76	76	
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQ. FT	2252	2252	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1200	1200	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1125	1125	
78001110	PAINT PAVEMENT MARKING LINE - 4"	FOOT	11,803	11,803	
78001180	PAINT PAVEMENT MARKING LINE - 24"	FOOT	146	146	
78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	13	13	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	47	47	