



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 28, 2024

SUBJECT: MUN 2080 & MUN 2100 (Wellington Ave. & Leicester Rd.)
Section 19-00070-00-BR (Elk Grove Village)
Cook County
Contract No. 61K21
Item 104
November 8, 2024 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Plan Sheets 31 & 39**
- 2. Revised page 64 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

Special Provisions
181136.40

Village of Elk Grove
Lake Cosman Bridges
19-00070-00-BR
Cook County
Contract 61K21

to the satisfaction of the Owner. No finish coating is required on the sample panel.

Method of Measurement: The exposed surfaces will be measured in place and the area computed in square feet.

Basis of Payment: Color staining will be paid for at the contract unit price per square foot for STAINING CONCRETE STRUCTURES. Anti-graffiti coating will be paid for at the contract unit price bid per square foot for ANTI-GRAFFITI COATING.

PARAPET RAILING (SPECIAL)

Description. This item shall include the furnishing of all materials and the labor necessary to construct and erect the completed railing to the lines and grades as shown on the plans and as specified herein. The line and grade of the railing shall be true to that shown on the plans and not follow any defects in the top of the retaining wall. Railing posts shall be vertical. Tops of railings shall be parallel to the grade line.

Materials. Materials shall meet the applicable requirements of Article 509.02 of the Standard Specifications.

Submittals. The railing supplier shall submit complete shop drawings to the Engineer no later than 90 days prior to beginning construction of the railing. No work or ordering of materials for the structure shall be done by the Contractor until the submittal has been approved in writing by the Engineer. All submittals shall include all plans, elevations, expansion joint locations, details, dimensions, quantities and cross sections necessary to construct the steel railing.

Construction. This item shall meet the applicable construction requirements of Articles 509.03, 509.04 and 509.05 of the Standard Specifications and all posts, railings, pickets, splices and anchor devices shall be finished using one coat of zinc-rich primer and two coats of a black powder-coated finish. Rail elements shall be powder coated internally as well as externally. The powder coating system to be used shall be approved by the Engineer prior to the beginning of fabrication. The Contractor shall submit to the Engineer for approval a sample of the final powder coated finish.

Method of Measurement. Railing will be measured in feet. The length paid for will be the overall length along the top longitudinal railing through all posts and gaps.

Basis of Payment. Railing will be paid for at the contract unit price per foot for PARAPET RAILING, (SPECIAL), which price shall include all materials, fabrication, transportation, erection, cleaning, priming, and powder coating.

A