

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	1201-2	OGLE	59	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

78001110 PAINT PAVEMENT MARKING - LINE 4"

<u>FOOT</u>	<u>LOCATION</u>
	IL 72
1320	Sta 2106+35 - 2112+95 LT - White EOP (2 Applications)
330	Sta 2106+35 - 2112+95 CL - Yellow Skip Dash (2 Applications)
1320	Sta 2106+35 - 2112+95 RT - White EOP (2 Applications)
3060	Sta 2112+95 - 2128+25 LT - White EOP (2 Applications)
6120	Sta 2112+95 - 2128+25 CL - Double Yellow No Pass (2 Applications)
3060	Sta 2112+95 - 2128+25 RT - White EOP (2 Applications)
1390	Sta 2128+25 - 2135+20 LT - White EOP (2 Applications)
2780	Sta 2128+25 - 2135+20 CL - Double Yellow No Pass (2 Applications)
1390	Sta 2128+25 - 2135+20 RT - White EOP (2 Applications)
<u>20,770</u>	TOTAL

78100100 RAISED REFLECTIVE PAVEMENT MARKER

<u>EACH</u>	<u>LOCATION</u>
	IL 72
2	Sta 2109+33 - 2110+09 Two-way Amber @ 80' o.c.
2	Sta 2131+10 - 2132+18 Two-way Amber @ 80' o.c.
<u>4</u>	TOTAL

78300100 PAVEMENT MARKING REMOVAL

<u>SQ FT</u>	<u>LOCATION</u>
	IL 72
55.0	Sta 2106+35 - 2112+95 Stage 1 - Centerline (Skip Dash)
111.7	Sta 2108+00 - 2111+35 Stage 1 - EOP (LT)
101.7	Sta 2108+15 - 2111+20 Stage 2 - EOP (RT)
463.3	Sta 2128+25 - 2135+20 Stage 3 - Centerline (Double Yellow)
141.7	Sta 2129+50 - 2133+75 Stage 4 - EOP (LT)
120.0	Sta 2129+85 - 2133+45 Stage 4 - EOP (RT)
<u>993.4</u>	TOTAL

A2006714 TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED

<u>EACH</u>	<u>LOCATION</u>
	IL 72
25	As directed by the Landscape Architect
<u>25</u>	TOTAL

C2001736 SHRUB, CORNUS SERICEA CARDINAL (CARDINAL REDOSIER DOGWOOD), 3' HEIGHT, BALLED AND BURLAPPED

<u>EACH</u>	<u>LOCATION</u>
	IL 72
34	As directed by the Landscape Architect
<u>34</u>	TOTAL

X0323988 TEMPORARY SOIL RETENTION SYSTEM

<u>SQ FT</u>	<u>LOCATION</u>
	IL 72
360	Sta 2109+64.78
454	Sta 2131+60
<u>814</u>	TOTAL

Z0005400 BREAKER-RUN CRUSHED STONE

<u>TON</u>	<u>LOCATION</u>
	IL 72
159.4	Sta 2109+64.78 (113' X 18.58' X 1.0') / 27' X 20.5
169.0	Sta 2131+60 (119.8' X 18.58' X 1.0') / 27' X 20.5
<u>328.4</u>	TOTAL

Z0020900 ESTABLISHING AND REFERENCING LAND SECTION MARKERS

<u>EACH</u>	<u>LOCATION</u>
	IL 72
1	Sta 2107+43.78 4.76' RT
1	Sta 2133+72.74 2.25' LT
<u>2</u>	TOTAL

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SCALE: VERT. DATE
HORIZ. DRAWN BY
CHECKED BY