CONTRACT NO. 60B16

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1627	0102.11-1	COOK	13	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

INDEX OF SHEETS

1. COVER PAGE
2. INDEX OF SHEETS, GENERAL NOTES, STATE STANDARDS
3. SUMMARY OF QUANTITIES
4 TRAFFIC CONTROL PLANS
5.-12. BRIDGE PLANS (SN 016-0918)
13. TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURE

LIST OF STATE STANDARDS

701101-01	OFF-ROAD OPERATIONS, MULTILANE, 4.5 M (15') TO 600 MM (24") FROM PAVEMENT EDGE
701206-01	LANE CLOSURE, 2L, 2W NIGHT ONLY, FOR SPEEDS >= 45 MPH
701301-02	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701400-02	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-03	LANE CLOSURE, FREEWAY/EXPRESSWAY
701801-03	LANE CLOSURE, MULTILANE, 1W OR 2W CROSS WALK OR SIDEWALK CLOSURE
702001-06	TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E" AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

IT SHALL BE THE CONTRACTORS RESPONIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRATOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 (FOR ARTERIALS) AND (847) 705-4451 (FOR EXPRESSWAYS) A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE SIGN PANELS ARE STORED AT NEW LENOX SIGN SHOP. THE CONTRACTOR SHALL CONTACT CORNELIUS SHANAHAN AT (847) 705-4501

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

ANY OPEN HOLES IN THE SIDEWALK SHALL PROPERLY BE COVERED WITH STEEL PLATES AFTER THE DAYS WORK TO ALLOW BICYCLE TRAFFIC.

CONCRETE SUPERSTRUCTURES SHALL HAVE A SEVEN DAY MINIMUM CURE.

THE CONTRATOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.

THE "ADVANCED WARNING SIGN DETAIL FOR ARTERIAL TRAFFIC" LOCATED IN THE SPECIAL PROVISIONS FOR "TEMPORARY INFORMATION SIGNING FOR LANE CLOSURES" IS APPLICABLE ONLY TO ARTERIAL ROADS AND SHALL NOT BE APPLIED TO EXPRESSWAYS.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS
GENERAL NOTES
AND STATE STANDARDS
GLENWOOD-LANSING/ IL 394

SCALE: VERT. HORIZ. DRAWN BY
DATE CHECKED BY

PLOT DATE = 9/1/2006
FILE NAME = c:\pr0jects\d129106\design-ea.dgn
PLOT SCALE = 60.0000 ' / IN.
USER NAME = bgurnick