
CONTRACT NO. 66372


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
627	(I-1) BR & I	LA SALLE	106	76
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED.	AID PROJ	ECT

OF 26 SHEETS

SHEET NO. H16




### TOP PLATE




## BOTTOM PLATE

See bearing details for pintle hole locations when required.



### LIFTING LOOP DETAIL



NOTES:

NOTES:

1.) Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270.

2.) The nominal diameter shall be '2' and the nominal cross-sectional area shall be 0.153 sq, in.

3.) Non-prestressing steel shall conform to AASHTO designation M-31 or M 322, Grade 60.

4.) A minimum 2'y' \( \) lifting pin shall be used to engage the lifting loops during handling.


5.) Reinforcement bars designated (E) shall be epoxy coated.


6.) Cut 66 bars when necessary to maintain 12' clearance.


7.) The bottom plates and studs shall be galvanized according to AASHTO MIII and ASTM A385.

8.) Threaded rods shall be ASTM F 1554 Grade 55.

9.) The cut strands at each beam end shall be given two coats of zinc dust spray or paint meeting the requirements of ASTM A 780. The zinc dust spray or paint shall be applied before corrosion appears and allowed to dry according to the manufacturer's specifications prior to another coat of zinc. A concrete sealer meeting the requirements of Section 587 of the Standard Specifications shall be applied to all portions of the 1-beam or Bulb-T beam, except the top surface of the top flange and the bottom surface of the bottom flange, starting at each beam end and extending out a distance of 42 inches. The sealer shall be applied after visible crack growth has subsided. This work shall be performed by the producer and included with the cost of the beam.







BAR G4

BAR G5

### BILL OF MATERIAL

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete I-Beams, 42"	Ft.	434

# 42" PPC I-BEAM DETAILS

IL ROUTE 71 OVER TRIBUTARY TO ILLINOIS RIVER F.A.P. ROUTE 627 - SEC. (I-1) BR & I LA SALLE COUNTY STATION 465+35.39 STRUCTURE NO. 050-0239

**PI-4-42D** 7-15-05

J.M.L.	Farnsworth	24-6772
DRAWN BY D. J.M.	GROUP 2700 NicGraw Drive	05-12-06
CHECKED BY	Sloomington, Illinois 51704	76 os 106