



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 1, 2023

SUBJECT: FAS 772 (Lebanon Road)  
Section 10-04106-00-BR  
Madison County  
Contract No. 97790  
Item 107  
November 17, 2023 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised Plan Sheets 8, 207, & 244**
- 3. Revised page 33 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment


## COMPLETION DATE

All work specified in this Contract shall be completed and all roads open to traffic on or before the Completion Date which is 12:00 PM, Friday, November 30, 2025. Should the Contractor not complete the work on or before the defined Completion Date, liquidated damages as specified in Article 108.09 of the Supplemental Specifications shall apply.

## TREE REMOVAL

As part of the effort to conserve the Federally Endangered Indiana and Northern Long-Eared Bat, standing trees three (3) inches or greater in diameter at breast height shall not be cut and cleared from April 1 through September 30. Notice to proceed will be issued sufficiently in advance of April 1 to allow the tree removal to be completed prior to April 1, 2024.

All labor, equipment, and materials required to complete this work will be included in the contract unit prices for the various tree removal pay items in the contract.



## FENCE REMOVAL

Description. This work shall consist of the complete removal and disposal of existing fence of different types including any gates, posts, supports, foundations, and associated hardware at locations shown in the plans, as directed by the Engineer, and in accordance with applicable portions of Section 201 of the Standard Specifications, and as herein specified.

Posts shall be pulled not broken off at the ground.

All post foundation holes shall be backfilled in a manner meeting the approval of the Engineer with the cost included in the unit price for FENCE REMOVAL.

All removed fencing material shall be legally disposed of off-site by the Contractor.

Method of Measurement. This work will be measured for payment in feet.

Basis of Payment: This work will be paid for at the contract unit price per foot for FENCE REMOVAL, which price shall be payment in full for all labor, equipment, and materials necessary to perform the work as herein specified.