326 (5CS,13C,108,109)R KENDALL 931 4 STA. TO STA. FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT

CONTRACT NO. 66671

COMMITMENTS

COMMITMENTS ARE NOT TO BE ALTERED WITHOUT THE WRITTEN APPROVAL OF ALL PARTIES TO WHICH THE COMMITMENT WAS MADE.

- 1. THE CONTRACTOR SHALL NOTIFY ALL LOCAL FIRE, POLICE, EMERGENCY SERVICES, SCHOOLS, AND POST OFFICES AT LEAST 7 DAYS PRIOR TO ANY ROAD CLOSURES.
- 2. THE RESIDENT ENGINEER IS TO OBTAIN A LETTER-PERMIT GRANTING PERMISSION FROM THE CITY OF YORKVILLE FOR SPECIAL WASTE ON THE CORNER OF ORANGE STREET AND ILLINOIS ROUTE 47.
- 3. ACCESS TO THE ENTRANCE AT APPROXIMATE STATION 20+200 RT SHALL BE MAINTAINED AT ALL TIMES AND THE ENTRANCE SHALL BE WIDENED TO 10.6m AS SHOWN IN THE PLANS.
- 4. THE ENTRANCE AT STATION 20+415.131 RT SHALL BE CONSTRUCTED SOUTH OF THE CURRENT LOCATION AND WIDENED TO 7.2m AS SHOWN IN THE PLANS.
- 5. THE WALNUT TREE LOCATED ALONG RIVER STREET AT STATION 21+241.318 LT SHALL NOT BE DAMAGED OR REMOVED DURING CONSTRUCTION. TREE ROOT PRUNING SHALL BE UTILIZED TO MINIMIZE THE IMPACT TO THE TREE DURING CONSTRUCTION.
- 6. A TEMPORARY USE PERMIT HAS BEEN OBTAINED TO CONSTRUCT AN ADA COMPLIANT RAMP. SIDEWALK. AND SLOTTED IN THE ALLEYWAY LOCATED BETWEEN THE TWO BUILDINGS AT APPROXIMATELY STATION
- 7. A TEMPORARY USE PERMIT HAS BEEN OBTAINED TO REMOVE A TREE AND STUMP LOCATED AT APPROXIMATELY 1+080 LT ON VAN EMMON STREET. THE RESIDENT ENGINEER IS TO CONTACT AND CONFIRM THE WORK WITH THE PROPERTY OWNER PRIOR TO THE REMOVAL.
- 8. THE PROPERTY OWNER AT 102 W. FOX STREET SHALL BE NOTIFIED TO COORDINATE STAGING OF ENTRANCE CONSTRUCTION.
- 9. A TEMPORARY USE PERMIT HAS BEEN OBTAINED TO CONSTRUCT THE ENTRANCES AT APPROXIMATE STATION 22+050 LT. ENTRANCES SHALL BE CONSTRUCTION ONE AT A TIME AND THE PROPERTY OWNER SHALL BE NOTIFIED PRIOR TO THE START OF CONSTRUCTION.
- 10. THE PROPOSED SIDEWALK RAMP AND RAILING WORK AT 213 S. BRIDGE STREET MAY NEED TO BE ADJUSTED OR DELETED FROM THE PLANS DURING CONSTRUCTION TO ACCOMMODATE WORK PLANNED BY THE PROPERTY OWNER.
- 11. PROPERTY AND BUSINESS OWNERS AT STATION 21+372 SHALL BE NOTIFIED WHEN CONSTRUCTION ACTIVITIES WILL BE DONE IN THE AREA.
- 12. TREE PROTECTION IN ACCORDANCE WITH ARTICLE 201.06 SHALL BE UTILIZED FOR THE LARGE FIR TREE LOCATED AT APPROXIMATELY STATION 20+510 RT.
- 13. THE RESIDENT ENGINEER SHALL CONTACT THE PROPERTY OWNER OF 102 APPLE TREE COURT PRIOR TO THE REMOVAL OF THE EXISTING ENTRANCE.
- 14. PARCEL 3KC0050 504 S BRIDGE ST SPEEDWAY:
 - A. TO ALLOW FOR FUEL DELIVERY TWO (2) ACCESS POINTS (30' WIDE) SHALL BE MAINTAINED AT ALL TIMES. PROPOSED DRIVEWAY SHALL BE "HIGH-EARLY CONCRETE".
 - B. ANY TEMPORARY ACCESS POINTS CONSTRUCTED SHALL BE OF STRUCTURALLY ADEQUATE MATERIAL AND MAINTAINED BY IDOT.
 - C. COMPENSATION WAS MADE TO SPEEDWAY TO ABANDON, FILL AND REINSTALL VARIOUS MONITORING WELLS (MW-1R, MW-1, MW-H, MW-7). CONTACT ENVIRONMENTAL REPRESENTATIVE MIKE MUSSELMAN (937-863-7071) WHO WILL COORDINATE THE FILLING OF THE WELLS AT SPEEDWAYS EXPENSE. SPEEDWAY WILL REQUIRE HELP FROM IDOT TO LOCATE 2 WELLS (MW-5 & MW-4R) TO BE FILLED. MONITORING WELLS TO BE REINSTALLED OUTSIDE OF RIGHT OF WAY AND ANY TEMPORARY EASEMENTS.
- 15. PARCEL 3KC0131 STA. 190+132.987 TO STA.190+511.307. THE RESIDENT ENGINEER SHALL CONTACT KATHLEEN HERRON (941-350-8653) PRIOR TO THE CONSTRUCTION OF THE PARKING LOT SO TENANTS CAN BE NOTIFIED.
- 16. PARCEL 3KC0101 101 A & B APPLE TREE COURT. THE RESIDENT ENGINEER SHALL CONTACT JOHN CHAPMAN (630-336-2052) PRIOR TO THE CONSTRUCTION OF THE DRIVE REMOVAL SO TENANTS CAN BE NOTIFIED.
- 17. PARCEL 3KC0132 STA. 190+151.307 TO STA. 190+181.833 LT:
 - A. PROPOSED ENTRANCE TO BE CONSTRUCTED AT EXISTING LOCATION.
 - B. INSTALL TEMPORARY FENCE (ORANGE SNOW FENCING) AT BACK EDGE OF TEMPORARY EASEMENT PRIOR TO CONSTRUCTION (BUT NOT UNTIL WORK BEGINS). FENCE SHALL REMAIN IN PLACE UNTIL CONSTRUCTION
 - C. A 30 DAY WRITTEN NOTICE SHALL BE MADE TO TIM POLK PERTAINING TO THE REMOVAL OF TWO LIGHT POLES FROM THE RIGHT OF WAY PRIOR TO ANY WORK BEGINNING ON THE PROPERY.

REVISIONS			_
NAME	DATE	ILLINOIS	C
BDD	BDD		

DEPARTMENT OF TRANSPORTATION

COMMITMENTS

DRAWN BY CHECKED BY