


SANITARY SEWER TEMPORARY BYPASS


DETAILS

DRAWN BY

CHECKED BY



## Bypass Pumping - Detail 2



Notes: 1) Siphon pipe & fittings to be constructed of PVC-SDR26 of the same diameter as existing sewer.

2) Lower part of siphon to be of one piece, centered on casing or carrier pipe.

Temporary Siphon

Contractor to construct temporary sump MH over existing sanitary sewer south of RR tracks, Jack 9.1m of 150mm casing pipe across tracks, and set up bypass pumping prior to construction of new sanitary sewer. Casing to be re-used for streetlight conduit.

FILE: 481-485W&S deta