

GENERAL NOTES

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
48	EXISTING BRIDGE PLANS (LOCATION NO 36, SN 099-4642)
49	EXISTING BRIDGE PLANS (LOCATION NO 37, SN 099-4648)
50	EXISTING BRIDGE PLANS (LOCATION NO 38, SN 099-9901)
51	EXISTING BRIDGE PLANS (LOCATION NO 39, SN 099-9904)
51A	EXISTING BRIDGE PLANS (LOCATION NO 39, SN 099-9904)
52	EXISTING BRIDGE PLANS (LOCATION NO 40, SN 022-2006)
53	EXISTING BRIDGE PLANS (LOCATION NO 41, SN 099-3013)
54	FREEWAY ENTRANCE AND EXIT RAMP CLOSURE DETAILS (TC-08)
54A	SINGLE LANE WEAVE AND MULTI-LANE WEAVE (TC-9)
55	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS INTERSECTIONS AND DRIVEWAY (TC-10)
56	TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER AND PARTIAL RAMP CLOSURES (TC-17)
57	ARTERIAL ROAD INFORMATION SIGN (TC-22)

STATE STANDARDS

<u>STANDARD NO.</u>	<u>DESCRIPTION</u>
701400-07	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-08	LANE CLOSURE, FREEWAY/EXPRESSWAY
701411-08	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP FOR SPEEDS > 456 MPH
701428	TRAFFIC CONTROL SETUP AND REMOVAL FREEWAY/EXPRESSWAY
701446-05	TWO LANE CLOSURE FREEWAY / EXPRESSWAY
701501-06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701502-06	URBAN LANE CLOSURE, 2L, 2W, BIDIRECTIONAL LEFT TURN LANE
701601-09	URBAN LANE CLOSURE, MULTILANE, 1L OR 2W, WITH NONTRAVERSABLE MEDIAN
701606-09	URBAN LANE CLOSURE, MULTILANE, 2W, WITH MOUNTABLE MEDIAN
701701-09	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-05	LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-03	TRAFFIC CONTROL DEVICES

EXISTING PAVEMENT MARKINGS SHALL BE TEMPORARILY COVERED PRIOR TO APPLICATION OF THE DECK SURFACE TREATMENT, TO PREVENT THE MATERIAL FROM BEING APPLIED TO THE MARKINGS. THE TEMPORARY COVERING SHALL BE REMOVED AFTER APPLICATION OF THE DECK SURFACE TREATMENT AND PRIOR TO OPENING TO TRAFFIC. COST IS INCLUDED WITH THE DECK SURFACE TREATMENT SPECIFIED.

FILE NAME =	USER NAME = Gorengoutab	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS STATE STANDARDS, GENERAL NOTES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwworking\pedco\gorengoutab\d8380535	D:\34514-shs-plandgn	DRAWN -	REVISED -		VAR	2014-0341	WILL&DUPAGE	57	2				
PLOT SCALE = 120.0000' / in.	CHECKED -	REVISED -			SCALE: NONE	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 60Y28		
PLOT DATE = 9/9/2014	DATE -	REVISED -			ILLINOIS FED. AID PROJECT								