

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

COUNTY TOTAL SHEET NO.

COOK 16 16

CONTRACT NO. 60766

FILE NAME =	USER NAME = gaglianobt	DESIGNED -	REVISED - R. MIRS 09-15-97						
W:\diststd\22x34\tc22.dgn		DRAWN -	REVISED - R. MIRS 12-11-97						
	PLOT SCALE = 50.000 ' / IN.	CHECKED -	REVISED -T. RAMMACHER 02-02-99						
L	PLDT DATE * 1/4/2898	DATE -	REVISED - C. JUCIUS 01-31-07						

STATE OF ILLINOIS						
DEPARTMENT	OF	TRANSPORTATION				

ARTERIAL ROAD					F.A.I.		SECTION		
				90/44		4-0	50 L	. ا	
							TC-2	2	
SCALE: NONE	SHEET NO. 1 OF 1	SHEETS	STA.	TO STA.	FEO. RO	AD DIST		ILLI	