

SUMMARY OF QUANTITIES				80/20 FED/STATE	100% STATE
				CONSTRUCTION CODE	
				6-10270-0000	6-10270-0400
				6-10270-0100	
				URBAN	
CODE		UNITS	TOTAL	ROADWAY	BOX CULVERT
				0005	0040
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	30	30	
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	7072	7072	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	97	97	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	367	367	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	120	120	
40600990	TEMPORARY RAMP	SQ YD	267	267	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1604	1604	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	918	918	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	240	240	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3756	3756	⚠
42400800	DETECTABLE WARNINGS	SQ FT	40	40	
44000600	SIDEWALK REMOVAL	SQ FT	3640	3640	
44200104	PAVEMENT PATCHING, TYPE I, 9 INCH	SQ YD	4	4	
44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SQ YD	254	254	