

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	SURVEILLANCE	BRIDGE SN 016-0088	BRIDGE SN 016-0090	BRIDGE SN 016-0086 SN 016-2758	BRIDGE SN 016-0085 SN 016-0986 SN 016-2759	TRAFFIC SIGNS 90% FED. 10% STATE
					90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	
					CONSTRUCTION TYPE CODE						
					X002-2A	Y032-1F	X020-2A	X071-2A	X231-2A	X271-2A	Y002-1C
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	109	109						
*	72000105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	228							228
	<del>70300220</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 4"</del>	<del>FOOT</del>	<del>89,798</del>	<del>89,798</del>						
*	72000205	SIGN PANEL - TYPE 2 (SPECIAL)	SQ FT	1,578							1,578
	<del>70300230</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 5"</del>	<del>FOOT</del>	<del>32,486</del>	<del>32,486</del>						
*	72000305	SIGN PANEL - TYPE 3 (SPECIAL)	SQ FT	12,166							12,166
	70300240	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	38,204	38,204						
*	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	15							15
	<del>70300250</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 8"</del>	<del>FOOT</del>	<del>27,451</del>	<del>27,451</del>						
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	558							558
	<del>70300260</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 12"</del>	<del>FOOT</del>	<del>4,366</del>	<del>4,366</del>						
*	73000105	WOOD SIGN SUPPORT, SPECIAL	FOOT	1,098							1,098
	<del>70301000</del>	<del>WORK ZONE PAVEMENT MARKING REMOVAL</del>	<del>SQ FT</del>	<del>49,243</del>	<del>49,243</del>						
*	84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	65							65
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	24,190	24,190						
*	X0326838	REMOVE SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	142							142
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	17,626	17,626						
*	X0326839	REMOVE SIGN PANEL - TYPE 2 (SPECIAL)	SQ FT	796							796
	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	617	617						
*	X0326840	REMOVE SIGN PANEL - TYPE 3 (SPECIAL)	SQ FT	11,099							11,099
	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	166,850	166,850						
*	X0326841	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL)	EACH	55							55
	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	937	937						
*	X0326842	MILE POST MARKER ASSEMBLY (SPECIAL)	EACH	28							28
	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	47,190	47,190						
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	15,231	15,231						
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	123	123						
*	78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	2,048	2,048						
*	78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	39,841	39,841						
*	78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,000	1,000						
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4,278	4,278						
*	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	446,804	446,804						
	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	80	80						
*	78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	119,608	119,608						
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	17,617	17,617						
*	78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	41,679	41,679						
	78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	3,281	3,281						
*	78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	84	84						
	78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	1,226	1,226						
*	78200450	MONODIRECTIONAL GUARDRAIL REFLECTORS	EACH	300	300						
	<del>70200400</del>	<del>MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR</del>	<del>EACH</del>	<del>4,524</del>	<del>4,524</del>						
*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	1,935	1,935						
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	30,301	30,301						
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4,278	4,278						
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	100		100					
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1						
*	88600100	DETECTOR LOOP, TYPE I	FOOT	170	170						
	X0326844	ROADSIDE DETECTOR	EACH	24		24					
	X0301424	SILICONE JOINT SEALER	FOOT	886.5			228.0	199.5	237.0	222.0	
	X0326845	SERVICE PROVIDER	CAL MD	12		12					
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	2,081	2,081						
	X0326846	ATMS INTERFACE	L SUM	1		1					
	X0322729	MATERIAL TRANSFER DEVICE	TON	105,640	105,640						
	X0326847	TEMPORARY DETECTION SYSTEM MONTHLY MAINTENANCE	CAL MD	12		12					
	X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2						
	X0326848	TEMPORARY DETECTION SYSTEM REMOVE AND SALVAGE	L SUM	1		1					
	X0325201	SHOULDER RUMBLE STRIP REMOVAL	SQ YD	362	362						
	X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	42			32		10		
	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	50						50	
	X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1						

\* Specialty Items

FILE NAME =	DESIGNED - AJP	REVISED -	<b>benesch</b>	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...prpIn_ABC_C2_sq_02.dgn	DRAWN - TMB	REVISED -							290	(3031.1, ETC., 383BRS-5	COOK	298	4
USER NAME = tblank	CHECKED - JMM	REVISED -			SCALE: N.T.S.	SHEET NO. 2 OF 3 SHEETS	STA.	TO STA.	CONTRACT NO. 60G52				
PLT DATE = 10/16/2009	DATE - 10/16/09	REVISED -							FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
Rev.													