

EASTBOUND SIGN SCHEDULE (CONTINUED)

SIGN NO.	STATION	LEGEND/DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL-TYPE 1 (SQ FT)	REMOVE SIGN PANEL-TYPE 2 (SQ FT)	REMOVE SIGN PANEL-TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A EACH	REMOVE SIGN PANEL ASSEMBLY - TYPE B EACH	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN PANEL TYPE 3 (SQ FT)	WOOD SIGN SUPPORT (FOOT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	REMOVAL OF SIGN LIGHTING, NO SALVAGE (EACH)			
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)														
EB-TR-78	715+30	EXIT 21A - DES PLAINES AVE - 1/2 MILE	18.5	7.5	18.5	7.5			138.8					138.8			1.0			
EB-WP-78A	719+92	DES PLAINES RIVER	4.0	2.0	7.8	2.5				1.0			19.4	138.8	18.0					
EB-CL-79	734+30	EXIT 21A - DES PLAINES - AVE	18.5	8.5	18.5	8.5			157.3					157.3			1.0			
EB-PM-79A	738+55	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					20.0							
EB-WP-80	739+15	EXIT 21A	7.5	5.0	7.0	5.0								35.0	36.0					
EB-TR-81	741+70	LEFT EXIT 21B - IL 43 HARLEM AVE - LEFT 1/2 MILE	18.5	10.5	18.5	10.5			194.3					194.3			1.0			
EB-TR-82	741+70	LEFT EXIT 23A - AUSTIN BLVD - LEFT 2 MILES	18.5	7.5	18.5	7.5			138.8					138.8			1.0			
EB-TS-82A*	748+99	DES PLAINES AVE	7.8	2.5	7.8	2.5										18.0				
EB-BM-83	769+75	LEFT EXIT 21B - IL 43 - HARLEM AVE	19.5	9.5	19.5	9.5			185.3				19.4	185.3			1.0			
EB-BM-83A*	769+75	CIRCLE AVE	7.0	1.5	7.0	1.5		10.5					10.5							
EB-PM-83B	771+51	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					20.0							
EB-WP-84	772+50	EXIT 21B	7.5	5.0	7.0	5.0								35.0	36.0					
EB-PM-84A*	779+50	ILL RTE 43 - HARLEM AVE	7.7	2.5	7.7	2.5		19.2					19.2							
EB-TS-84B	789+15	W4-1L	4.0	4.0	4.0	4.0								16.0		18.0				
EB-BM-84C*	794+70	HOME AVE	7.0	1.5	7.0	1.5		10.5					10.5							
EB-PM-84D1	801+58	M3-2	2.5	1.3	2.5	1.3	3.1													
EB-PM-84D2	801+58	M1-1-3 (I 290)	PER MUTCD STD (9FT ²)		PER MUTCD STD (9FT ²)		9.0					3.1	9.0							
EB-PM-84E	805+64	R2-1 (55 MPH)	4.0	5.0	4.0	5.0		20.0					20.0							
EB-BM-85	808+65	LEFT EXIT 23A - AUSTIN BLVD - LEFT 3/4 MILE	15.5	8.5	15.5	8.5			131.8					131.8			1.0			
EB-BM-86	808+65	EXIT 23B - CENTRAL AVE - RIGHT 1 1/4 MILES	17.5	8.5	17.5	8.5			148.8					148.8			1.0			
EB-BM-86A*	808+65	OAK PARK AVE	8.8	1.5	8.8	1.5		13.1					13.1							
EB-PM-86B	812+35	TRUCKS - USE - 2 - RIGHT - LANES	4.0	5.0	4.0	5.0		20.0					20.0							
EB-GM-87	820+80	CHICAGO CITY LIMITS 1 - CHICAGO DOWNTOWN 9	24.5	5.0	25.5	5.5			122.5					140.3						
EB-BM-88	822+10	LEFT EXIT 23A - AUSTIN BLVD - LEFT 1/2 MILE	18.0	8.0	18.0	8.0			144.0					144.0			1.0			
EB-BM-88A*	822+10	EAST AVE	6.0	1.5	6.0	1.5	9.0					9.0								
EB-BM-88B*	835+56	RIDGELAND AVE	9.3	1.5	9.3	1.5		13.9					13.9							
EB-BM-89	849+20	LEFT EXIT 23A - AUSTIN BLVD - 6000 W	20.5	7.5	20.5	7.5			153.8					153.8			1.0			
EB-BM-89A*	849+20	LOMBARD AVE	8.5	1.5	8.5	1.5		12.8					12.8							
EB-PM-89B	851+17	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					20.0							
EB-WP-90	855+22	EXIT 23A	7.5	5.0	7.0	5.0								35.0	36.0					
EB-BM-91	862+60	EXIT 24B - IL 50 CICERO AVE - 1 1/4 MILES	20.0	9.5	20.0	9.5			190.0					190.0			1.0			
EB-BM-92	862+60	EXIT 23B - CENTRAL AVE - RIGHT 1/4 MILE	16.0	9.5	16.0	9.5			152.0					152.0			1.0			
EB-BM-92A*	862+60	AUSTIN BLVD - 6000 W	7.7	2.5	7.7	2.5		19.2					19.2							
EB-WP-92B	871+89	W4-3L	4.0	4.0	4.0	4.0								16.0	18.0					
EASTBOUND SUBTOTAL										67	360	5350	9	36	121	891	5760	630	396	34

*EXISTING SIGN DIMENSIONS NOT AVAILABLE; PROPOSED SIGN DIMENSIONS USED

FILE NAME =	DESIGNED - SEW	REVISED -
FILE#	DRAWN - SEW	REVISED -
USER NAME = #USER#	CHECKED - FML	REVISED -
PLOT DATE = #DATE#	DATE - 12/2009	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(3031L, ETC., 3830RS-5	COOK	413	300
CONTRACT NO. 60G52				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				