

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET NO.	SHE
FAI 55		Will		72	33	19
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-			
Contract	#620	30	;	* 88(88	R- IIRR	

Contract #62930

88(B&B-1)BR

еет но. 5 SHEETS

BILL OF MATERIAL <u>2 PIE</u>RS

Bar	No.	Size	Length	Shape
a(E)	88	#7	25'-3''	
a3(E)	96	#6	4'-3''	
d(E)	28	#5	5'-0''	
d1(E)	28	#5	3'-1''	
х(Е)	168	#6	9′-5″	L
Concret	'e Remo	Cu. Yd.	52.7	
Concret	e Super	Cu. Yd.	56.3	
Reinfor Epoxy		Pound	7770	

MIN. BAR LAP #7 bars = 2'-9"

NOTES:

Existing longitudinal reinforcement and dowel rods extending into the removed areas shall be cleaned, straightened and incorporated into the new construction. Cost included with Concrete Removal.

Hatched areas indicate deck to be removed as Concrete Removal. Removal of existing neoprene joint is included

Removal. Removal or existing neoprene joint is included with Concrete Removal. The parapet within the limits of the deck to be removed is also to be removed as Concrete Removal. Any longitudinal reinforcement bars extending into the New Construction that are demand during concrete removal abeli

Construction that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete Removal.

ILLINOIS DEPARTMENT OF TRANSPOR	RTATION
SHEET TITLE	
EXPANSION JOINT DETAILS PIERS	4 & 8
I-55 NB OVER KANKAKEE RIVER FAI ROUTE 55, SECTION 88(B&B-1)BR WILL COUNTY SN 099-0001	PROJECT NO. 03095-16 SCALE 6/25/09 DRAWN BY TFG/CFC CHECKED BY MCB
COOMBE-BLOXDORF P.C.	DRAWING NO.
Engineers / Land Surveyors Springfield, Illinois	5
Design Firm License No. 184-002703	OF 19 SHTS