ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET NO.	SHEET NO. $2$	
FAI 55	*	Will		72	49	9	SHEETS
FED. ROAD DIST. NO. 7		ILL INOIS	PED. AIO PROJECY-				

Contract #62930

\* 88(B&B-1)BR

## INDEX OF SHEETS

- 1 PLAN AND ELEVATION
- 2 GENERAL NOTES AND TOTAL BILL OF MATERIAL
- 3 CROSS SECTION
- 4 CONTINUOUS SEAL NEOPRENE EXPANSION JOINTS
- 5-6 DECK SLAB REPAIR
- 7 CONCRETE BRACKETS AT PIERS
- 8 PIER REPAIRS
- 9 ABUTMENT AND PIER REPAIRS

## GENERAL NOTES

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

THE CONTRACTOR SHALL ENSURE THAT NO CONCRETE WILL BE ALLOWED TO DROP INTO THE RIVER. CONCRETE SHALL BE CAUGHT ON A FLOATING PLATFORM OR OTHER MEANS APPROVED BY THE ENGINEER. COST INCLUDED WITH DECK SLAB REPAIR (FULL DEPTH, TYPE II).

REINFORCEMENT BARS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A 760 GR 60. SEE SPECIAL PROVISIONS.

REINFORCEMENT BARS DESIGNATED (E) SHALL BE EPOXY COATED.

## TOTAL BILL OF MATERIAL

ITEU	LIMITT	SUPER	CUD	TOTAL
ITEM	UNIT	SUPER	SUB	TOTAL
Bridge Deck Latex Concrete Overlay 2'4"	Sg Yd	4449		4449
Bridge Deck Hydro Scarification 1"	Sg Yd	4449		4449
Neoprene Expansion Joint $2^{l_2}$ "	Foot	97		97
Neoprene Expansion Joint 4"	Foot	97		97
Epoxy Crack Injection	Foot		275	275
Structural Repair of Concrete	Sq Ft		00	90
(Depth equal to or less than 5")			90	1
Concrete Removal	Cu Yd		8.0	8.0
Concrete Structures	Cu Yd		29.5	29.5
Reinforcement Bars, Epoxy Coated	Pound		3,090	3,090
Polymer Concrete	Cu Ft	0.5		0.5
Deck Slab Repair (Full Depth, Type I)	Sq Yd	1		1
Bridge Deck Grooving	Sq Yd	4219		4219
Protective Coat	Sq Yd	4449		4449

ILLINOIS DEPARTMENT OF TRANSPORTATION GENERAL NOTES AND TOTAL BILL OF MATERIAL I-55 SB OVER KANKAKEE RIVER FAI ROUTE 55, SECTION 88(B&B-1)BR WILL COUNTY G/25/09

ORAWN BY
TFG/CFC
CHECKED BY
MCB/KPS
DRAWING NO. SN 099-0002 COOMBE-BLOXDORF P.C. Engineers / Land Surveyors Springfield, Illinois Design Firm License No. 184-002703 OF 9 SHTS

DATE NAME SCALE NAME