



4-1" Dla. X 5'-0" (4-25.4 Dla. X 1.524 m)





ANCHOR ROD DETAIL

(2.74 m)

8'-3" (2.52 m)

7'-9" (2.36 m)


9'-0" (2.74 m)


MEDIUM SAND # = 37.5°

DENSE SAND Ø = 40°

6" (152.4) THREADED

%" T. X 4" Dlg. (15.87 T. X 101.6 Dlg.) WASHER, TACK WELDED





## **NOTES**

- 1. ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.
- THE ANCHOR RODS AND RACEWAYS SHALL BE PROPERLY SECURED IN PLACE BEFORE THE CONCRETE IN PLACED.
- 3. THE FOUNDATION SHALL NOT PROTRUDE MORE THAN JOOMM (4 IN.) ABOVE THE FINISHED GRADE WITHIN A 60 IN. (1.5 m) CHORD ACROSS THE FOUNDATION, WITH ANCHOR ROOS INCLUDED, IN ACCORDANCE WITH ASSITO GUIDELINES, IF THE FOUNDATION HEIGHT, INCLIDING ANCHOR ROOS, EXTENDS BEYOND THESE SPECIFED LIMITS, THE FOUNDATION SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE. SEE FOUNDATION EXTENSION DETAIL.
- 4. THE HOLE FOR THE FOUNDATION SHALL BE MADE BY DRILLING WITH AN AUGER, OF THE SAME DIAMETER AS THE FOUNDATION. IF SOIL CONDITIONS REQUIRE THE USE OF A LINER TO FORM THE HOLE, THE LINER SHALL BE WITHORAWN AS THE CONCRETE IS DEPOSITED.
- 5. THE TOP OF THE FOUNDATION SHALL BE CONSTRUCTED LEVEL, A LINER OR FORM SHALL BE USED TO PRODUCE A UNIFORM SMOOTH SIDE TO THE TOP OF THE FOUNDATION, FOUNDATION TOP SHALL BE CHAMFERED  $\frac{1}{2}$ -IN, (20 mm).
- THE CONCRETE SHALL BE CLASS SI. CONCRETE SHALL CURE ACCORDING TO ARTICLE 1020.13 BEFORE LIGHT POLES ARE INSTALLED.
- THE ANCHOR ROD SHALL BE A HOOK ROD TYPE. COLD BENDING OF THE ANCHOR ROD WILL NOT BE ALLOWED. THE RADIUS OF THE HOOK BEND SHALL NOT BE LESS THAN 4 TIMES THE NOMINAL DIAMETER OF THE ANCHOR ROD. A TACK WELDED ANCHOR ROD MAY BE SUBSTITUTED WITH THE
- 8. THE ANCHOR RODS SHALL BE ACCORDING TO ASTM F1554 GRADE 725 (GRADE 105). NUTS SHALL BE HEXACON NUTS ACCORDING TO ASTM A 194 2H OR ASTM A 563 DH, AND WASHERS SHALL BE ACCORDING TO ASTM F 436.
- ANCHOR RODS, NUTS AND WASHERS SHALL BE COMPLETELY GALVANIZED BY EITHER THE HOT-DIPPED PROCESS CONFORMING WITH AASHTO M 232, THE MECHANICAL PLATING METHOD CONFORMING TO AASHTO M 298, CLASS 50 WITH A MAXIMUM COATING THICKNESS OF 150 LIMIG MILS) OR THE ELECTROLYTIC PROCESS ACCORDING TO ASTM F 1136.
- 10. THE ANCHOR RODS SHALL BE THREADED A MINIMUM OF 6 INCHES (150 mm) WITH A MINIMUM OF 3 INCHES (75 mm) OF THREADED ANCHOR ROD EMBEDDED IN THE FOUNDATION.
- ANCHOR RODS SHALL PROJECT 234" (69.9 mm) ABOVE THE TOP OF THE FOUNDATION. IF BREAKAWAY COUPLINGS ARE SPECIFIED, THE CONTRACTOR SHALL CAREFULLY COORDINATE THE ANCHOR ROD PROJECTION WITH THE INSTALLATION REQUIREMENTS OF THE BREAKAWAY COUPLINGS.
- THE CONTRACTOR SHALL USE A \*3 SPIRAL AT 6" (152.4 mm) PITCH OR MAY SUBSTITUTE \*3 TIES AT 12" (304.8 mm) O.C. WITH THE APPROVAL OF THE ENGINEER.
- 13. THE CABLE TRENCHES AND FOUNDATION SHALL BE BACK FILLED AND COMPACTED AS SPECIFIED BEFORE THE LIGHT POLE IS ERECTED.
- 14. THE RACEWAYS SHALL PROJECT 1" (25.4 mm) ABOVE THE TOP OF THE FOUNDATION.

	R	0		b	ĺ	ŋ	5		0	n	1
groot See:	N	69	(Sage	M	gros Pas	1900 1967 1900		(E.S.O.)	M	Ps.	

FILE NAME = 09321-DTLS-01 - P05 USER NAME = DESIGNED — PAP REVISED -OAK AVE. TO WENTWORTH AVE. SECTION CHECKED -- EJT REVISED — STATE OF ILLINOIS LIGHT POLE FOUNDATION 40' TO 47.5' MOUNTING HEIGHT COOK 12 11 1683 09-00166-01-LT DRAWN — MJD PLOT SCALE = N/A 15" BOLT CICRLE DETAILS REVISED --DEPARTMENT OF TRANSPORTATION CONTRACT NO. 63285 PLOT DATE = 10-19-09 CHECKED - DWS REVISED SCALE: N/A SHEET NO. 11 OF 12 SHEETS STA. N/A TO STA. N/A FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT 9003(335)