

FED. ROAD DIST. NO. 1 | ILLINOIS | CONTRACT NO. 63307





NOTES

- A: MAINLINE ROADWAYS AND MAJOR SIDE ROADS.
- B: MINOR SIDE ROADS.
- C: THE TEMP. RAMP SHALL BE CONSTRUCTED IMMEDIATELY UPON REMOVAL OF THE EXISTING HMA SURFACE.
- D: THE BUTT JOINT SHALL BE CONSTRUCTED IMMEDIATELY PRIOR TO PLACING THE PROPOSED HMA COURSES.
- E: TAPER THE TEMP. RAMP AT A RATE OF 3'-0" (900 mm) PER 1 INCH (25 mm) OF MILLING THICKNESS.
- INSTALLATION AND REMOVAL OF THE 4'-6" (1.35 m) TEMP. RAMP IS INCLUDED IN COST OF HMA SURFACE REMOVAL - BUTT JOINT
- G: SEE ARTICLE 406.08 AND 406.14 OF THE STANDARD SPECIFICATIONS FOR "HMA AND/OR PCC SURFACE REMOVAL, BUTT JOINT".
- * SEE TYPICAL SECTIONS FOR MILLING THICKNESS.
- 20'-0" (6.1 m) PER 1 (25) RESURFACING (NOTE "A") 10'-0" (3.0 m) PER 1 (25) RESURFACING (NOTE "B")

BASIS OF PAYMENT:

- THE BUTT JOINT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE
- PER SQUARE YARD (SQUARE METER)
 FOR "HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT" OR FOR "PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT"

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

ILLINOIS PROFESSIONAL DESIGN FIRM NO. 184-002235

TECH 3 Consulting Group, Inc. **ENGINEERS** SURVEYORS 737 West Exchange St. Crete, IL 60417

ph 708.672.4994 fax 708.672.3739

Village of Flossmoor Flossmoor, Illinois

DESIGNED BY: RWM DRAWN BY: EGH

CHECKED BY: RWM

REVISIONS DESCRIPTION PER I.D.O.T. REVIEW 10/12/09

FLOSSMOOR ROAD RESURFACING **WESTERN AVENUE TO DIXIE HIGHWAY BUTT JOINT AND HOT MIX ASPHALT TAPER DETAILS**

OF 11