

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS		LIGHTS	SIGNALS
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE				
					1000	SFTY-1D		Y030-1E	Y031-1F
	20200100	EARTH EXCAVATION	CU YD	187	187				
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	10	10				
	20800150	TRENCH BACKFILL	CU YD	5	5				
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	321	321				
	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	300			200	100	
	25100630	EROSION CONTROL BLANKET	SQ YD	321	321				
	28000400	PERIMETER EROSION BARRIER	FOOT	618	618				
	28000500	INLET AND PIPE PROTECTION	EACH	2	2				
	28000510	INLET FILTERS	EACH	5	5				
	35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	142	142				
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	250	250				
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	233	233				
	44000100	PAVEMENT REMOVAL	SQ YD	141	141				
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	2091	2091				
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	344	344				
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	417	417				
	50105220	PIPE CULVERT REMOVAL	FOOT	69	69				
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2				
	54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	2	2				
	55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	5	5				
	55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	126	126				
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	1	1				
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2				
	60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	2	2				
	60500050	REMOVING CATCH BASINS	EACH	1	1				
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	544	544				
	67100100	MOBILIZATION	L SUM	1	1				
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1				
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1105		1105			
	72000100	SIGN PANEL - TYPE 1	SQ FT	18	18				
	72000200	SIGN PANEL - TYPE 2	SQ FT	15	15				
	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	25	25				
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	222		222			
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1888		1888			
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	430		430			
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	21		21			
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	74		74			
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	44		44			
*	78300100	PAVEMENT MARKING REMOVAL	SQ FT	74		74			
*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	44		44			
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	591					591
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	227					227
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	60					60
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	34					34
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	246			60		186
*	81400100	HANDHOLE	EACH	4					4
*	81400200	HEAVY-DUTY HANDHOLE	EACH	4					4

* - INDICATES SPECIALTY ITEMS

FILE NAME = 0587-QUAN-01 - 001	USER NAME =	DESIGNED -- BDB/JRA	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CHICAGO HEIGHTS-GLENWOOD ROAD AND HOLBROOK ROAD INTERSECTION IMPROVEMENTS SUMMARY OF QUANTITIES			F.A.U. RTE. 3603	SECTION 09-00050-00-TL	COUNTY COOK	TOTAL SHEETS 31	SHEET NO. 3
	PLOT SCALE =	DRAWN -- JRA	REVISED --		SCALE: N/A	SHEET NO. 3	OF 31 SHEETS	STA.	TO STA.	CONTRACT NO. 63320		
	PLOT DATE = 10-29-09	CHECKED -- JRA	REVISED --		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-9003 (332)							