

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS		LIGHTS	SIGNALS
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE				
					I000	SFTY-1D		Y030-1E	Y031-1F
*	81400300	DOUBLE HANDHOLE	EACH	1					1
*	81603050	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	625				625	
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1412				570	842
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	7				7	
*	83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	7				7	
*	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	2				2	
*	84200700	LIGHTING FOUNDATION REMOVAL	EACH	2				2	
*	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2				2	
*	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1					1
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	386					386
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1488					1488
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	198					198
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1185					1185
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	100					100
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	3					3
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1					1
*	87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1					1
*	87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1					1
*	87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1					1
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	29					29
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4					4
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	15					15
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15					15
*	88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	5					5
*	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	3					3
*	88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1					1
*	88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1					1
*	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	4					4
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	5					5
*	88600100	DETECTOR LOOP, TYPE 1	FOOT	700					700
*	88700200	LIGHT DETECTOR	EACH	2					2
*	88700300	LIGHT DETECTOR AMPLIFIER	EACH	1					1
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	357	357				
*	XX004574	UNINTERRUPTIBLE POWER SUPPLY AND TYPE III CABINET	EACH	1					1
*	XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	2			2		
	X0322054	REMOVAL OF PRECAST FLARED END SECTION	EACH	2	2				
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	77	77				
*	X8050015	SERVICE INSTALLATION POLE MOUNTED	EACH	1					1
*	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	464					464
*	X8730275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 20 3C	FOOT	386					386
	XY008245	SEEDING, CLASS 2A (SPECIAL)	SQ YD	321	321				
*	X8161000	EXPOSE AND RELOCATE EXISTING UNIT DUCT	FOOT	30			30		
*	X0323574	MAINTENANCE OF EXISTING LIGHTING SYSTEM	MONTH	5			5		

* - INDICATES SPECIALTY ITEMS

FILE NAME = 0587-QUAN-01 - 002	USER NAME =	DESIGNED -- BDS/JRA	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CHICAGO HEIGHTS-GLENWOOD ROAD AND HOLBROOK ROAD INTERSECTION IMPROVEMENTS SUMMARY OF QUANTITIES			F.A.U. RTE. 3603	SECTION 09-00050-00-TL	COUNTY COOK	TOTAL SHEETS 31	SHEET NO. 4
	PLOT SCALE =	DRAWN -- JRA	REVISED --		SCALE: N/A	SHEET NO. 4	OF 31 SHEETS	STA.	TO STA.	CONTRACT NO. 63320		
	PLOT DATE = 10-29-09	CHECKED -- JRA	REVISED --		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-8003 (332)							