INDEX OF SHEETS

- 1.) COVER SHEET, INDEX TO SHEETS, LOCATION MAP, INDEX OF STANDARDS
- 2.) SUMMARY OF QUANTITIES
- 3.) GENERAL NOTES
- 4.) TYPICAL SECTIONS
- 5.) PLAN 107TH STREET
- 6.) PLAN 107TH STREET
- 7.) PLAN HARLEM AVENUE
- 8.) PLAN RIDGELAND AVENUE
- 9.) DETAIL SHEET
- DETAIL SHEET BD-01
- 11.) DETAIL SHEET BD-02
- 12.) DETAIL SHEET BD-24
- 13.) DETAIL SHEET TC-13

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

PLANS FOR PROPOSED

FEDERAL AID HIGHWAY

107TH STREET - HARLEM AVENUE TO OAK PARK AVENUE - FAU 1679 HARLEM AVENUE - CAL SAG CANAL BRIDGE TO 116TH STREET - FAP 0348 RIDGELAND AVENUE - CAL SAG BRIDGE TO HOME AVENUE - FAU 2781 **SIDEWALK**

> SECTION NO.: 09-00058-00-SW PROJECT NO. ARA-9003(392) JOB NO. C-91-772-09

IO. 1679, FAP ROUTE NO. 0348, FAU ROUTE NO. 2781

VILLAGE OF WORTH WORTH TOWNSHIP COOK COUNTY

LIST OF ILLINOIS DOT HIGHWAY STANDARDS

000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS	FAU ROUTE NO
280001-04	TEMPORARY EROSION CONTROL SYSTEMS	
424001-05	CURB RAMPS FOR SIDEWALKS	
606001-04	CONCRETE CURB TYPE B AND COMBINATION	
	CONCRETE CURB & GUTTER	

BEGIN IMPROVEMENT

HARLEM AVE. STA. 9+65

BEGIN IMPROVEMENT HARLEM AVE. STA. 0+50

664001-02 CHAIN LINK FENCE

701006-03 OFF ROAD OPERATIONS

LANE CLOSURE - SHORT OPERATIONS 701301-03


701501-05 URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED

701801-04 LANE CLOSURE MULTILANE 1W OR 2W


CROSSWALK OR SIDEWALK CLOSURE

701901-01 TRAFFIC CONTROL DEVICES

PROFILE HORIZ. 1 INCH = 30 FEET SCALES < PROFILE VERT. 1 INCH = 5 FEET CROSS-SECTIONS HORIZ. 1 INCH = 10 FEET CROSS-SECTIONS VERT. 1 INCH = 5 FEET



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.






1"=1200

LOCATION OF SECTION INDICATED THUS:

SECTION

P.H.W.A. REG. | ILLINOIS | PROJECT: ARA-9003(392)

COUNTY



ENGINEER'S CERTIFICATION STATE OF ILLINOIS)

COUNTY OF DUPAGE)

PRINTED BY AUTHORITY OF THE STATE OF ILLINOIS

LOCATION MAP - DENOTES PROJECT LOCATION

NET LENGTH OF PROJECT = 4626 LIN FT (0.88 MILE) GROSS LENGTH OF PROJECT = 4626 LIN FT (0.88 MILE)

FIELD ENGINEER: MELCHOR MANGOBA MORRIS ENGINEERING, INC. (630) 271

CONTRACT NO. 63330