

CONTRACT NO. 63347

SIDEWALK REMOVAL AND REPLACEMENT SCHEDULE																					
STA	SIDE	SIDEWALK REMOVAL WIDTH (FT)	SIDEWALK REMOVAL LENGTH (FT)	44000600 SIDEWALK REMOVAL (SQ. FT)	PCC SIDEWALK WIDTH (FT)	PCC SIDEWALK LENGTH (FT)	42400200 PCC SIDEWALK, 5" (SQ. FT)	DETECTABLE WARNINGS WIDTH (FT)	DETECTABLE WARNINGS LENGTH (FT)	DETECTABLE WARNINGS (SQ. FT)	STA	SIDE	SIDEWALK REMOVAL WIDTH (FT)	SIDEWALK REMOVAL LENGTH (FT)	44000600 SIDEWALK REMOVAL (SQ. FT)	PCC SIDEWALK WIDTH (FT)	PCC SIDEWALK LENGTH (FT)	42400200 PCC SIDEWALK, 5" (SQ. FT)	DETECTABLE WARNINGS WIDTH (FT)	DETECTABLE WARNINGS LENGTH (FT)	DETECTABLE WARNINGS (SQ. FT)
130+55	RT	4	5	20	4	5	20	2	4	8	163+83	RT	4	5	20	4	5	20			
131+00	RT	6	5	30	6	5	30	2	4	8	164+83	LT	5	5	25	5	5	25			
131+80	RT	5	5	25	5	5	25	2	4	8	164+45	RT	4	5	20	4	5	20	2	4	8
132+82	RT	5	5	25	5	5	25	2	4	8	165+94	RT	4	6	24	4	6	24	2	4	8
132+98	RT	5	5	25	5	5	25	2	4	8	166+71	LT	5	10	50	5	10	50	2	4	8
133+21	RT	5	5	25	5	5	25	2	4	8	167+05	LT	5	10	50	5	10	50	2	4	8
140+91	LT	5	5	25	5	5	25				167+14	RT	7	8	56	7	8	56	2	8	16
142+82	LT	5	15	75	5	15	75				168+65	LT	5	5	25	5	5	25			
143+05	LT	4	9	36	4	9	36	2	4	8	168+95	RT	13	5	65			0			
146+29	LT	5	6	30	5	60	300				168+95	LT	5	5	25	5	5	25			
148+18	LT	4	12	48	4	12	48				170+36	LT	5	5	25	5	5	25	2	4	8
151+15	RT	4	21	84	4	21	84				170+81	LT	5	5	25	5	5	25			0
151+50	RT	4	9	36	4	9	36				171+89	LT	4	5	20	4	5	20			0
152+10	RT	4	6	24	4	6	24	2	4	8	172+19	RT	4	15	60			0			
152+10	LT	4	5	20	4	5	20	2	4	8	172+22	RT	4	4	16	4	4	16	2	4	8
152+61	RT	4	6	24	4	6	24	2	4	8	172+36	LT	4	9	36	4	9	36	2	4	8
152+61	LT	4	5	20	4	5	20	2	4	8	182+52	LT	4	5	20	4	5	20	2	4	8
153+05	LT	4	5	20	4	5	20	2	4	8	172+84	RT	9	5	45	9	5	45			0
153+40	LT	4	9	36	4	9	36	2	4	8	172+85	LT	4	5	20	4	5	20			0
154+39	LT	4	16	64	4	16	64				172+90	RT	4	5	20	4	5	20	2	4	8
154+75	RT	4	32	128	4	32	126				172+90	LT	4	5	20	4	5	20	2	4	8
155+13	LT	4	5	20	4	5	20				173+55	RT	4	8	32	4	8	32			
155+45	LT	4	5	20	4	5	20	2	4	8	174+00	RT	4	15	60	4	15	60			
155+94	LT	4	5	20	4	5	20	2	4	8	174+26	RT	4	30	120	4	30	120	2	4	8
156+00	LT	4	15	60			0				174+74	LT	5	10	50	4	10	40			
157+14	LT	4	10	40	4	10	40				174+91	RT	4	5	20	4	5	20	2	4	8
157+89	RT	4	10	40	4	10	40				175+86	RT	4	5	20	4	5	20			0
159+00	RT	4	10	40	4	10	40	2	4	8	176+14	RT	4	5	20	4	5	20			0
159+05	RT	4	6	24	4	6	24	2	4	8	176+60	RT	4	6	24	4	6	24	2	4	8
159+42	LT	4	10	40	4	10	40				177+00	RT	14	3	42	14	3	40	2	4	8
159+50	RT	4	5	20	4	5	20	2	4	8	177+15	RT	4	5	20	4	5	20			
159+55	RT	4	14	55			0				177+50	RT	4	10	40	4	10	40			
161+00	RT	4	20	80	4	20	80				178+76	LT	5	16	80	4	16	64			
161+86	LT	5	5	25	5	5	25				179+00	LT	5	5	25	5	5	25	2	4	8
161+90	RT	4	5	20	4	5	20				179+19	LT	5	5	25	5	5	25	2	4	8
162+22	LT	5	5	25	5	5	25				179+90	RT	5	5	25	5	5	25	2	4	8
162+77	LT	5	5	25	5	5	25							81	9	9	81	2	6	12	
															2700			2700			300
															SF			SF			SF

DRIVEWAY SCHEDULE	
LOCATION	XX006947 HOT MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT (SQ. YD.)
VARIOUS LOCATIONS BETWEEN STA. 130+00 TO 134+00	40
VARIOUS LOCATIONS BETWEEN STA. 144+00 TO 152+00	140
VARIOUS LOCATIONS BETWEEN STA. 153+00 TO 159+00	130
VARIOUS LOCATIONS BETWEEN STA. 160+00 TO 165+00	175
VARIOUS LOCATIONS BETWEEN STA. 167+00 TO 172+50	65
	550
	SY

NOTE:
ALL QUANTITIES SHOWN IN THE SCHEDULES ARE APPROXIMATE. THE ENGINEER WILL LOCATE ALL IMPROVEMENTS IN THE FIELD PRIOR TO CONSTRUCTION. PAYMENT SHALL BE BASED ON ACTUAL FIELD MEASUREMENTS.

VILLAGE OF WOODRIDGE PUBLIC WORKS
1 Plaza Drive, Woodridge IL 60517 (630) 719-4753

**JANES AVENUE
REHABILITATION PROJECT**

SCHEDULE OF QUANTITIES

DRAWN BY: AF CHECKED BY: SM