

CONTRACT NO. 63347

CURB AND GUTTER REMOVAL AND REPLACEMENT SCHEDULE		
STA.	SIDE	44001700 CURB AND GUTTER REMOVAL AND REP. LENGTH (FT)
129+20	RT	7
129+30	LT	70
131+20	RT	30
131+70	RT	22
132+38	RT	33
133+00	RT	38
133+10	LT	60
133+95	RT	10
134+55	RT	10
136+72	RT	8
136+95	RT	11
137+48	LT	12
138+60	LT	16
139+27	RT	23
139+80	RT	13
141+50	RT	10
143+00	LT	17
145+28	RT	10
145+75	RT	12
146+54	RT	7
146+93	RT	10
147+28	RT	57
148+73	RT	12
149+08	RT	30
149+94	RT	65
150+00	LT	16
151+65	RT	20
152+53	RT	26
154+75	RT	15
156+00	LT	35
156+42	RT	14
157+98	RT	36
161+10	RT	7
161+28	LT	8
162+25	LT	16
162+50	RT	11
163+40	RT	58
164+05	LT	25
164+70	LT	30
165+60	LT	70
165+95	RT	20
166+56	LT	18
167+20	RT	54
167+25	LT	66
168+26	LT	6
168+60	RT	48
169+48	RT	15
169+75	LT	15
170+22	RT	19
170+90	RT	5
171+53	RT	14
171+85	RT	11
172+00	RT	5
172+15	RT	18
174+80	RT	11
		1305
		FOOT

PATCHING SCHEDULE									
STA.	SIDE	PATCH WIDTH (FT)	PATCH LENGTH (FT)	PATCH AREA (SQ. FT.)	20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU. YD.)	20700420 POROUS GRANULAR EMBAKMENT SUBGRADE (CU. YD.)	44201705 CLASS D PATCHES TYPE II, 5" (SQ. YD.)	44201709 CLASS D PATCHES TYPE III, 5" (SQ. YD.)	44201711 CLASS D PATCHES TYPE IV, 5" (SQ. YD.)
138+85	RT	8	50	400	10	10			44
143+22	LT	13	10	130			14		
148+60	LT	12	18	216				25	
153+71	RT	12	28	336					37
153+92	LT	12	8	96			11		
156+00	LT	12	30	360					40
163+75	LT	12	25	300					33
167+55	LT	12	18	216				25	
167+75	RT	12	75	900	20	20			100
169+80	LT	12	41	492	20	20			55
171+20	LT	12	30	360					40
					50	50	25	50	350
					CY	CY	SY	SY	SY

DRAINAGE AND UTILITY STRUCTURE SCHEDULE						
STA.	SIDE	60255500 MANHOLES TO BE ADJUSTED (EACH)	60260100 INLETS TO BE ADJUSTED (EACH)	60262700 INLETS TO BE RECONSTRUCTED (EACH)	60265700 VALVE VAULTS TO BE ADJUSTED (EACH)	60300310 FRAME AND LIDS TO BE ADJUSTED (SPECIAL) (EACH)
130+75	LT		1			
133+80	LT	1				
151+94	RT		1			
155+65	LT	1				
159+75	RT			1		
159+75	LT		1			
164+40	RT			1		
164+40	LT		1			
165+50	RT	1				
166+00	RT	1				
166+90	LT					1
170+20	LT	1				
170+80	RT		1			
170+80	LT			1		
172+80	RT		1			
174+70	LT				1	
176+20	LT		1			
178+20	LT					1
179+60	RT					1
179+70	LT					1
179+80	RT					1
179+80	LT					1
179+85	RT					1
		5	7	3	1	7
		EA	EA	EA	EA	EA

NOTE:
ALL QUANTITIES SHOWN IN THE SCHEDULES ARE APPROXIMATE. THE ENGINEER WILL LOCATE ALL IMPROVEMENTS IN THE FIELD PRIOR TO CONSTRUCTION. PAYMENT SHALL BE BASED ON ACTUAL FIELD MEASUREMENTS.

VILLAGE OF WOODRIDGE PUBLIC WORKS
1 Plaza Drive, Woodridge IL 60517 (630) 719-4753

**JANES AVENUE
REHABILITATION PROJECT**

SCHEDULE OF QUANTITIES