INDEX OF SHEETS

- COVER SHEET AND INDEX OF SHEETS
- general notes, highway standards, and summary of quantities
- 3 TYPICAL SECTIONS
- 4-6 PLAN SHEETS
- 7-9 PAVEMENT MARKING SHEETS
- 10 BD-08 FRAMES AND LIDS ADJUSTMENT WITH MILLING
- 11 BD-22 PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT
- 12 BD-24 CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT
- 13 RD-32 RUTT JOINT AND HMA TAPER DETAILS
- 14 TC-10 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS
- 15 TC-13 DISTRICT ONE TYPICAL PAVEMENT MARKINGS
- 16 TC-16 PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING
- 17 TC-22 ARTERIAL ROAD INFORMATION SIGN
- 18 TC-26 DRIVEWAY ENTRANCE SIGNING
- 19 TS-07 DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING

FOR INDEX OF HIGHWAY STANDARDS, SEE SHEET NO. 2

TRAFFIC DATA

ADT:

LIES ROAD 12,600 VPD (2008)

16,000 VPD (2030)

POSTED SPEED

35 MPH (EXISTING)

40 MPH (EXISTING)

DESIGN SPEED


35 MPH (PROPOSED)

40 MPH (PROPOSED)

PROJECT IS LOCATED IN THE VILLAGE OF CAROL STREAM

DESCRIPTION OF IMPROVEMENT

THIS IMPROVEMENT CONSISTS OF A 3" MILL AND 3" RESURFACING, REMOVING AND REPLACING DETERIORATED PORTIONS OF CURB AND GUTTER AND SIDEWALKS, PAVEMENT PATCHING, STRUCTURE ADJUSTMENTS OR RECONSTRUCTION, STRIPING, AND ALL INCIDENTAL AND COLLATERAL WORK AS NECESSARY TO COMPLETE THE IMPROVEMENT SHOWN HEREIN AND AS DESCRIBED IN THE SPECIFICATIONS.



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123 OR 811

CONTRACT NO. 63369


STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

PLANS FOR PROPOSED FEDERAL AID HIGHWAY PROJECT

FAU ROUTE 1375 (LIES ROAD)
KUHN ROAD TO GARY AVENUE
LAPP RESURFACING
SECTION 09-00054-00-RS
PROJECT ARA-9003(400)
DUPAGE COUNTY
JOB NO. C-91-807-09



LOCATION MAP

NOT TO SCALI


PROJECT LENGTH (GROSS /NET) LIES ROAD 5,386 FT (1.02 MILES)



PROJECT ENDS

STATION 157+93

DAVID W. BLOCK, P.E. NO. 062-050966 EXP. DATE 11/30/09 



Deputy DIRECTOR OF HIGHWAYS, REGION 1 ENGINEER

PRINTED BY THE AUTHORITY
OF THE STATE OF ILLINOIS

REVIEW OCTOBER 26, 2009