

GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 650 (IL 78)	104T-2	JoDaviess	53	5
FED ROAD DIST. NO.	ILLINOIS	PROJECT		
Contract #64C79				

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Commonwealth Edison Co.
NICOR Gas Co.

Verizon
Mediacom

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

No section of guardrail shall be removed until such time that removal is necessary to complete work in that area. This is necessary to protect motorists from hazards in the clear zone. When guardrail is removed, the hazard that was protected shall be alleviated within 48 hours or protected with a longitudinal barrier and/or temporary impact attenuator at no cost to the department. The barrier and temporary impact attenuator layout shall be approved by the department prior to installation.

The Class C Patches shall be placed according to Section 442 of the Standard Specifications. Class PP-2 or PP-3 concrete conforming to Section 1020.04 and 1020.05(b)(5) of the Standard Specifications shall be utilized for this patch. No additional compensation shall be allowed for the work, but shall be included in the contract unit price per Square Yard for CLASS C PATCHES, TYPE IV, 10 INCH.

The Contractor shall not have Field Tile Junction Vault ordered or constructed until exploratory trench is used to determine depth of existing field tile.

The Contractor shall notify Rinker Materials Concrete Pipe Division in Buffalo, IA to order the reinforced concrete arch pipe. Rinker Materials Concrete is the only producer on the approved list that makes this type of pipe. Elliptical or round pipes will not be allowed as a substitution.

Tie bars are required for Class C Patches more than 20'-0" in length. No additional compensation shall be allowed for the work, but shall be included in the contract unit price per Square Yard for CLASS C, PATCHES, TYPE IV, 10 INCH.