

# SCHEDULE OF QUANTITIES

35101400	AGGREGATE BASE COURSE, TYPE B					
	LOCATION				TON	REMARKS
	STA 895 + 00	TO	STA 900 + 50	RT	146	CHELSEA ROAD - SHOULDER
	STA 895 + 00	TO	STA 900 + 50	LT	146	CHELSEA ROAD - SHOULDER
	STA 896 + 74.95			LT	58	CHELSEA ROAD - FIELD ENTRANCE
	STA 967 + 65.95			LT	66	MEYER ROAD - FIELD ENTRANCE
				TOTAL	416	
40600990	TEMPORARY RAMP				SQ YD	REMARKS
	LOCATION					
	STA 969 + 08.68	RT			13	MEYER ROAD
	STA 969 + 08.68	LT			13	MEYER ROAD
	STA 969 + 48.26	RT			13	MEYER ROAD
	STA 969 + 48.26	LT			13	MEYER ROAD
				TOTAL	52	
40603310	HOT-MIX ASPHALT SURFACE COURSE,		MIX "C", N50		TON	REMARKS
	LOCATION					
	STA 895 + 00	TO	STA 900 + 50		120	CHELSEA ROAD - SHOULDERS
	STA 897 + 38.33	TO	STA 898 + 15.59		32	CHELSEA ROAD
	STA 897 + 38.33	TO	STA 898 + 15.59	RT	9	CHELSEA ROAD - SHOULDER (STAGE II)
	STA 966 + 50	TO	STA 972 + 25.07	RT	63	MEYER ROAD - SHOULDERS
	STA 966 + 50	TO	STA 971 + 00	LT	49	MEYER ROAD - SHOULDERS
	STA 969 + 08.68	TO	STA 969 + 48.26		16	MEYER ROAD
				TOTAL	289	
44004250	PAVED SHOULDER REMOVAL				SQ YD	REMARKS
	LOCATION					
	STA 897 + 38.33	TO	STA 898 + 15.59		61	CHELSEA ROAD - STAGE II
				TOTAL	61	
44201359	CLASS C PATCHES, TYPE IV, 10 INCH				SQ YD	REMARKS
	LOCATION					
	STA 897 + 38.33	TO	STA 898 + 15.59		224	CHELSEA ROAD
	STA 969 + 08.68	TO	STA 969 + 48.26		115	MEYER ROAD
				TOTAL	339	
48101200	AGGREGATE SHOULDERS, TYPE B				TON	REMARKS
	LOCATION					
	STA 966 + 50	TO	STA 971 + 00	LT	159	MEYER ROAD - TRAFFIC CONTROL
	STA 966 + 50	TO	STA 972 + 25.07	RT	230	MEYER ROAD - TRAFFIC CONTROL
				TOTAL	389	
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"				SQ YD	REMARKS
	LOCATION					
	STA 895 + 00	TO	STA 900 + 50		856	CHELSEA ROAD
	STA 897 + 38.33	TO	STA 898 + 15.59	RT	61	CHELSEA ROAD - SHOULDER (STAGE II)
	STA 966 + 50	TO	STA 972 + 25.07	RT	448	MEYER ROAD
	STA 966 + 50	TO	STA 971 + 00	LT	350	MEYER ROAD
				TOTAL	1715	