

MAINLINE										
LOCATION	LENGTH	AVERAGE WIDTH	BIT MAT'L PR CT	AGG PRIME COAT	MIX CR, JT, & FLGWY	LEV BIND (HM) N70	LEV BIND (MM) N70	HMA SURF CSE "D", N70	HMA SURF REM 1 1/2"	TEMP RAMP
STA TO STA	FOOT	FOOT	GAL	TON	TON	TON	TON	TON	SQ YD	SQ YD
4+23 TO 5+40	117	37	63	1.0	0.1	0.2	13	44	481	20.6
5+40 TO 9+19	379	50	274	4.2	0.6	1.1	42	200	2106	
9+19 TO 12+46	327	58	274	4.2	0.6	1.1	37	203	2107	
12+46 TO 15+10	264	65.75	251	3.9	0.6	1.0	30	188	1929	
15+10 TO 17+74	264	58	221	3.4	0.5	0.9	30	164	1701	
17+74 TO 19+14	140	53	107	1.6	0.2	0.4	16	79	824	
19+14 TO 22+14	300	49.5	215	3.3	0.5	0.8	34	156	1650	
22+14 TO 40+78	1864	32	862	13.3	2.0	3.3	209	592	6628	17.8
<b>TOTALS</b>			<b>2265</b>	<b>35</b>	<b>5.2</b>	<b>8.7</b>	<b>409</b>	<b>1625</b>	<b>17426</b>	<b>38</b>

SIDE STREET SCHEDULE												
MAINLINE STATION	SIDE	LOCATION	TYPE	LENGTH FT	WIDTH FT	AREA SQ YD	HMA SURF REM 1 1/2" SQ YD	LEVEL BINDER (MM) TONS	INC HMA SURF TONS	AGG PRIME COAT TONS	TEMP RAMPS SQ YD	BIT MAT PR CT GALLON
5+64	RT	STATE ST	HMA	18	27	60	60		5	0.1	15.0	5
5+80.5	LT	CH 13	HMA	91	32	361	361		30	0.7	17.8	29
5+80.5	LT	STATE ST	HMA	14	25	49	49		4	0.1	13.9	4
9+07.5	RT	WASHINGTON ST	HMA	85	24	228	228	10	19	0.5	13.3	30
9+25	LT	WASHINGTON ST	HMA	85	48	391	391	10	36	0.8	26.7	51
12+73	LT	MONROE ST	HMA	11	50	48	48		4	0.1	27.8	4
15+28	RT	EMMETT ST	HMA	15	40	74	74		6	0.1	22.2	6
16+01	LT	EMMETT ST	HMA	12	50	64	64		5	0.1	27.8	5
18+62.5	RT	GENOA ST	HMA	17	32	71	71		6	0.1	17.8	6
18+83	LT	GENOA ST	HMA	15	44	77	77		6	0.2	24.4	6
21+75.5	LT	SYCAMORE ST	HMA	91	32	336	336	10	30	0.7	17.8	44
21+75.5	RT	SYCAMORE ST	HMA	83	32	309	309	9	28	0.6	17.8	40
25+35	LT	LOCUST ST	HMA	18	34	83	83		7	0.2	18.9	7
25+35	RT	LOCUST ST	HMA	18	32	76	76		6	0.2	17.8	6
28+95	LT	ALLEY	HMA	17	12	39	39		3	0.1	6.7	3
30+91	LT	STOTT ST	HMA	20	36	89	89		7	0.2	20.0	7
30+91	RT	STOTT ST	HMA	19	36	83	83		7	0.2	20.0	7
32+84	LT	ALLEY	HMA	17	12	39	39		3	0.1	6.7	3
34+77	LT	BROWN ST	HMA	25	34	109	109		9	0.2	18.9	9
34+77	RT	BROWN ST	HMA	20	32	81	81		7	0.2	17.8	6
37+09	LT	ALLEY	HMA	17	15	39	39		3	0.1	8.3	3
38+79	RT	HADSALL ST	HMA	20	32	76	76		6	0.2	17.8	6
39+02	LT	HADSALL ST	HMA	17	30	82	82		7	0.2	16.7	7
<b>TOTALS</b>							<b>2864</b>	<b>39</b>	<b>248</b>	<b>6</b>	<b>412</b>	<b>292</b>

SIDEWALK SCHEDULE FOR NEW RAMP INSTALLATION							
LOCATION SIDESTREET QUAD	PCC SIDEWALK 4" SQ FT	DETECTABLE WARNINGS SQ FT	CC&G (SPEC) FOOT	SIDEWALK REMOVAL SQ FT	CC&G REMOV (SPEC) FOOT	SOD, SALT TOLERANT SQ YD	EARTH EXCAV CU YD
CH 13	NO EXISTING SIDEWALK						
STATE ST							
SW	60	8		60		7	0.6
NW	60	8	16	60	16	7	0.6
SE	60	8		60			
NE	60	8	16	60	16	7	0.6
WASHINGTON ST							
SW	180	16	36	180	36	7	0.6
NW	180	16	36	180	36	7	0.6
SE	480	16	36	480	36		
NE	180	16	36	180	36	7	0.6
MONROE ST							
SOUTH	120	8	36	120	36	7	0.6
NW	480	16	36	480	36		
NE	480	8	36	480	36		
EMMETT ST							
SW	240	8	16	240	16		
SE	480	16	36	480	36		
NW	480	16	36	480	36		
NE	480	8	36	480	36		
GENOA ST							
SW	480	16	36	480	36	3	0.3
NW	480	16	36	480	36		
SE	120	16	36	120	36	15	1.2
NE	240	8	16	240	16		
SYCAMORE ST							
NW	480	16	36	480	36	3	0.3
SW	180	16	36	180	36		
NE	120	16	36	120	36	15	1.2
SE	180	16	36	180	36	7	0.6
LOCUST ST							
NW	120	16	43	120	43	15	1.2
SW	120	16	43	120	43	15	1.2
NE	120	16	43	120	43	15	1.2
SE	120	16	43	120	43	15	1.2
STOTT ST							
NW	120	16	43	120	43	15	1.2
SW	120	16	43	120	43	15	1.2
NE	120	16	43	120	43	15	1.2
SE	120	16	43	120	43	15	1.2
BROWN ST							
NW	60	8	16	60	16	7	0.6
SW	60	8	16	60	16	7	0.6
NE	60	8	16	60	16	7	0.6
SE	60	8	16	60	16	7	0.6
HADSALL ST							
NW	120	16	43	120	43	15	1.2
SW	120	16	43	120	43	15	1.2
SE	60	8	16	60	16	7	0.6
NE	180	8	16	180	16	20	1.8
<b>TOTALS</b>	<b>7980</b>	<b>504</b>	<b>1202</b>	<b>7980</b>	<b>1202</b>	<b>297</b>	<b>25</b>

FILE NAME =	USER NAME = verdnml	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\VPWIDOT\VERDINEM\vd0104085\d	66746 sht-cover.dgn	DRAWN -	REVISED -		553	(128)RS-4	DEKALB	13	5			
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -		SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. TO STA.			CONTRACT NO. 66746				
	PLOT DATE = Oct 05, 2009 - 02:30:44 PM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							