

PAVEMENT MARKINGS																
LOCATION IL RTE 72	THERMOPLASTIC							RAISED	RAISED	TEMPORARY PAINT					SHORT TERM (3 APP)	WORK ZONE PAVT MARK REM SQ FT
	4"		6"		8"	12"	24"	REFLECTIVE	REFL	(2 APPLICATIONS)						
	YELLOW	WHITE	YELLOW	WHITE	WHITE	WHITE	WHITE	PAVT MARK	PAVT	DOES NOT INCLUDE PARKING						
	NO PASS ZONE	EDGE & PARK	CENTER LINE	CROSS WALKS	ISLAND	ISLAND & CROSSWALKS	STOP BARS	TWO-WAY AMBER	MARK REMOV	FOOT	FOOT	FOOT	FOOT	FOOT		
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
4+23 TO 6+00		110	50					2		220	100				53	18
STATE ST RT				58				13.5			116					
CH 13 LT	40					122		149		80		244	298	32.0		
STATE ST LT	NO PAVEMENT MARKINGS															
6+00 TO 9+25		192	80	108		108		25.0	4		376		216	50.0	98	33
WASHINGTON ST RT			20	58				13.0			156			26.0		
WASHINGTON ST LT			20	64				15.0			168			30.0		
9+25 TO 12+50		194	80	235		231		25.0	4		630		462	50.0	98	33
MONROE ST LT				76				23.4			152			46.8		
12+50 TO 15+80		584	80	121		120			4		402		240		99	33
EMMETT ST RT				88				20.0			176			40.0		
EMMETT ST LT				96							192					
15+80 TO 18+80		186	80	113		114			4		386		228		90	30
GENOA ST RT				74				16.1			148			32.2		
GENOA ST LT				89				22.0			178			44.0		
18+80 TO 21+75		154	70	100		99		28.2	4		340		198	56.4	89	30
SYCAMORE ST LT			20	68				16.0			176			32.0		
SYCAMORE ST RT			20	82				16.6			204			33.2		
21+75 TO 25+35			90	80		81		16.0	5	5	340		162	32.0	108	36
LOCUST ST LT				72				16.3			144			32.6		
LOCUST ST RT				67				16.0			134			32.0		
25+35 TO 30+91			140						7	7	280				167	56
STOTT ST LT				73				17.5			146			35.0		
STOTT ST RT				74				17.5			148			35.0		
30+91 TO 34+77			100						5	5	200				116	39
BROWN ST LT				72				16.0			144			32.0		
BROWN ST RT				66				12.0			132			24.0		
34+77 TO 39+00	122		110	66		66			5	5	244		132		127	42
HADSALL ST RT				63				14.8			126			29.6		
HADSALL ST LT				66				11.2			132			22.4		
39+00 TO 40+78	178		40						2	2	356		80		53	18
SUBTOTALS	340	1420	1000	2129	122	968	387	46	24	900	6258	244	1936	774	1098	368
TOTALS	1760		3129		122	968	387	46	24	900	6258	244	1936	774	1098	368

FILE NAME =	USER NAME = verdinml	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\PWIDOT\VERDINML\d0104085\d366746-shr-cover.dgn		DRAWN -	REVISED -		553	(128)RS-4	DEKALB	13	6				
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -		SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. TO STA.				CONTRACT NO. 66746				
PLOT DATE = Oct 05, 2009 - 02:31:03 PM		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								