

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

STATION	O/S	EACH
273+00.18	29.80' RT	1.0
283+00.00	51.20' RT	1.0
285+50.00	73.71' RT	1.0
289+09.24	77.31' RT	1.0
289+76.31	77.99' RT	1.0
294+50.00	82.74' RT	1.0
269+20.00	84.45' RT	1.0
300+08.78	88.35' RT	1.0
299+99.95	56.26' RT	1.0
TOTAL =		9.0

CARE SHALL BE TAKEN NOT TO DISTURB ANY R.O.W. MARKERS NOT SHOWN ON THIS LIST. SHOULD THE CONTRACTOR DISTURB ANY ADDITIONAL MARKERS, THEY SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

XZ193300 SURVEY MARKER, TYPE 1(SPECIAL)

STATION	DESCR.	EACH
273+00.18	PC	1.0
274+21.01	PT	1.0
302+91.47	PC	1.0
303+88.57	PT	1.0
TOTAL =		4.0

RAISED REFLECTIVE PAVEMENT MARKERS

STATION	TO	STATION	LENGTH FOOT	78100100 RAISED REF PVT MKRS EACH	78100105 RRPM BRIDGE EACH	78300200 RRPM REM EACH
273+00.00		304+00.00	3100.00	36.0	3.0	36.0
TOTAL =				36.0	3.0	36.0

78001110 PAINT PAVEMENT MARKING LINE 4"

STATION	TO	STATION	LENGTH FOOT	WHITE EDGE LINE FOOT	YELLOW CENTER LINE SKIP DASH FOOT	YELLOW NO PASSING ZONE FOOT
273+00.00		304+00.00	3100.0	6200.0	1023.0	
LT 278+00.00		291+00.00	1300.0			1300.0
RT 287+90.00		299+50.00	1160.0			1160.0
SUB-TOTAL =				6200.0	1023.0	2460.0
TOTAL =				9683.0		

78001180 PAINT PAVEMENT MARKING LINE 24"

STATION	WHITE STOP BAR LENGTH FOOT	
0+35.73	22.0	
TOTAL =		22.0

ADDITIONAL SCHEDULE NOTES:

SEE G.N. Z0038 FOR INFORMATION CONCERNING PERMANENT BENCH MARKS

SEE SCHEDULES OF REMOVAL SHEET(S) 51-52

SEE SCHEDULES OF EROSION CONTROL SHEET(S) 59

SEE SCHEDULES OF DRAINAGE SHEET(S) 68

SEE GUARDRAIL DETAILS SHEET(S) 72