

SUMMARY OF QUANTITIES

FAP 697 (L 9)
 VERMILION COUNTY
 STATION 1304+13.46
 TO
 STATION 1305+18.54
 RURAL 2-LANE
 80% FEDERAL
 20% STATE
Y007

LOCATION OF WORK:

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY
54021004	PRECAST CONCRETE BOX CULVERT 10' X 4' (M273)	FOOT	90.0
60238800	INLETS, TYPE A	EACH	1.0
60402210	GRATES, TYPE B	EACH	1.0
*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	325.0
*63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	100.0
*63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	50.0
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	4.0
63200310	GUARDRAIL REMOVAL	FOOT	303.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1.0
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	237.0
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2.0
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	8.0
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2.0
Z0010555	DITCH CLEANING	FOOT	341.0
Z0038800	PERMANENT BENCH MARKS, TYPE I	EACH	1.0

*SPECIALTY ITEM

FILE NAME =	USER NAME = cealockjd	DESIGNED -	REVISED -
ca:\pw_work\pwsdot\cealockjd\09132042\09	70594-sh1-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 48.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/19/2009	DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
697	46BR	Vermilion	31	5
CONTRACT NO. 70594			ILLINOIS FED. AID PROJECT	