

SCHEDULE OF QUANTITIES – PARTIAL DEPTH PATCHING

EASTBOUND AND CENTER BI-DIRECTIONAL TURN LANE

STATION	LANE	EXISTING HMA THICKNESS (IN)	LENGTH (FT)	WIDTH (FT)	X4401705 PARTIAL DEPTH REMOVAL (SQ YD)	X4421000 PARTIAL DEPTH PATCHING (TON)
323+06	EBPL	2.5	6.0	12.0	8.0	2.5
323+10	EBDL	2.5	8.0	12.0	10.7	3.3
323+94	CBDTL	2.5	6.0	12.0	8.0	2.5
323+94	EBPL	2.5	6.0	12.0	8.0	2.5
323+94	EBDL	2.5	6.0	12.0	8.0	2.5
335+85	EBPL	2.5	8.0	12.0	10.7	3.3
336+71	EBPL	2.5	10.0	12.0	13.3	4.1
336+71	EBDL	2.5	10.0	12.0	13.3	4.1
337+24	CBDTL	2.5	8.0	12.0	10.7	3.3
337+24	EBPL	2.5	8.0	12.0	10.7	3.3
337+24	EBDL	2.5	8.0	12.0	10.7	3.3
343+20	CBDTL	2.5	8.0	12.0	10.7	3.3
343+20	EBPL	2.5	8.0	12.0	10.7	3.3
343+20	EBDL	2.5	8.0	12.0	10.7	3.3
343+91	EBPL	2.5	20.0	12.0	26.7	8.2
345+90	EB	3.25	20.0	12.0	26.7	9.3
348+08	EB	3.25	20.0	12.0	26.7	9.3
348+76	EB	3.25	6.0	12.0	8.0	2.8
349+29	EB	3.25	6.0	12.0	8.0	2.8
352+06	EB	3.25	30.0	12.0	40.0	14.0
354+38	EB	3.25	6.0	12.0	8.0	2.8
354+68	EB	3.25	6.0	12.0	8.0	2.8
358+24	EB	3.25	10.0	12.0	13.3	4.7
360+69	EB	3.25	16.0	12.0	21.3	7.5
360+86	EB	3.25	6.0	12.0	8.0	2.8
361+51	EB	3.25	6.0	12.0	8.0	2.8
362+48	EB	3.25	8.0	12.0	10.7	3.7
362+96	EB	3.25	6.0	12.0	8.0	2.8
366+03	EB	3.25	6.0	14.0	9.3	3.3
EAST BOUND AND CENTER TURN LANE TOTALS =					374.7	124.0

WESTBOUND LANES

STATION	LANE	EXISTING HMA THICKNESS (IN)	LENGTH (FT)	WIDTH (FT)	X4401705 PARTIAL DEPTH REMOVAL (SQ YD)	X4421000 PARTIAL DEPTH PATCHING (TON)
324+07	WBPL	2.5	6.0	12.0	8.0	2.5
324+41	WBDL	2.5	16.0	12.0	21.3	6.6
337+24	WBPL	2.5	8.0	12.0	10.7	3.3
337+24	WBDL	2.5	8.0	12.0	10.7	3.3
343+20	WBPL	2.5	8.0	12.0	10.7	3.3
343+20	WBDL	2.5	8.0	12.0	10.7	3.3
346+78	WB	3.25	20.0	12.0	26.7	9.3
348+08	WB	3.25	60.0	12.0	80.0	28.0
348+49	WB	3.25	20.0	12.0	26.7	9.3
348+76	WB	3.25	6.0	12.0	8.0	2.8
349+29	WB	3.25	6.0	12.0	8.0	2.8
349+64	WB	3.25	20.0	12.0	26.7	9.3
354+97	WB	3.25	6.0	12.0	8.0	2.8
360+69	WB	3.25	6.0	12.0	8.0	2.8
360+86	WB	3.25	6.0	12.0	8.0	2.8
361+51	WB	3.25	10.0	12.0	13.3	4.7
362+48	WB	3.25	8.0	12.0	10.7	3.7
362+96	WB	3.25	6.0	12.0	8.0	2.8
366+03	WB	3.25	6.0	14.0	9.3	3.3
WEST BOUND LANE TOTALS =					313.3	106.6

JOB TOTAL X4401705 PARTIAL DEPTH REMOVAL = 313.3 + 374.7 = 688.0 SQ YD
 ROUND TO 700.0 SQ YD

JOB TOTAL X4421000 PARTIAL DEPTH PATCHING = 124.0 + 106.6 = 230.6 TONS
 ROUND TO 235.0 TONS