



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 23, 2009

SUBJECT: FAP Route 662 (IL 4)
Project F-0662 (062)
Section D (W-3,RS-11,CR)
Macoupin County
Contract No. 72765
Item No. 199, January 15, 2010 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 6 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Roger Driskell, Region 4, District 6; Mike Renner; R. E. Anderson;
Estimates

TBW:DB:jc

This detector amplifier shall be programmed with 8 seconds of delay time. The temporary controller cabinet shall inhibit this delay time during green. The far loop shall be landed under a separate detector amplifier.

Alternative methods of detection such as microwave sensors, video detection or preformed loops may be used for side approaches where pavement conditions are not adequate for the construction of standard inductive loops.

A three (3) inch wide strip of reflective tape shall be applied to the perimeter of the face of all traffic signal back plates. The reflective tape shall be fluorescent yellow in color and shall consist of type AZ sheeting.

The Contractor shall notify the Engineer at least 72 hours in advance of activating the temporary signals. IDOT District 6 Operations Traffic Signal Section shall be contacted for controller programming and timing assistance.

Basis of Payment: Temporary signals required for Standards 701316 and 701321 will be paid for separately at the contract unit price each for TEMPORARY BRIDGE TRAFFIC SIGNALS.

Any relocation of the traffic signal equipment due to stage construction will not be paid for separately, but shall be included in the cost of the initial installation.

COMPLETION DATE

All work required in this contract shall be completed by **September 1, 2010**. Lane closures involving Traffic Control and Protection Standard 701321 will not be allowed before June 1, 2010, or after **September 1, 2010**. **Twenty-five (25)** additional working days will be allowed after **September 1, 2010**, for resurfacing and cleanup work.

If the Contractor fails to complete the required work by the completion date(s) or within the number of additional working days stated herein, he/she shall be liable to the Department for liquidated damages in accordance with Article 108.09 of the Standard Specifications and any other additional special provision which may be attached herein which supplements Article 108.09. The Contractor will also be liable for additional items of work made necessary by not meeting the completion date(s) or additional working days allowed. Such items include, but are not restricted to, temporary pavement marking, temporary erosion control, and temporary seeding.

STATUS OF UTILITIES TO BE ADJUSTED

The following utilities are involved in this project. The utility companies have provided the estimated dates.

Revised 12/23/2009