

NOTE 1: RIPRAP SHALL EXTEND FAR ENOUGH UP THE SLOPES TO ALLOW O. 3m (1') OVERTOPPING TO AVOID ERODING AROUND THE EDGES OF THE RIPRAP

NOTE 2: ENDS SHALL BE TIED INTO SLOPES.

## LEGEND FOR STORM WATER POLLUTION PREVENTION PLAN SYMBOL AGGREGATE (EROSION CONTROL) [STONE DUMPED RIPRAP DITCH CHECKS: Height = 0.6m (2') ] TEMPORARY DITCH CHECKS INLET PIPE PROTECTION (I&PP) EROSION CONTROL FENCE **✓** EARTH EXCAVATION FOR EROSION CONTROL (SEDIMENT BASINS) PRESERVE EXISTING TREES, WOODLANDS, AND UNDERSTORY (OUTSIDE CONSTRUCTION LIMITS) ITEM PLACED AT BEGINNING OF \* [ITEM \* CONSTRUCTION (Requirement) ITEM PLACED AS DIRECTED BY ITEM ENGINEER (When required by situation) DIRECTION OF OVERLAND FLOW

## GENERAL NOTES:

All items shall be constructed as shown on this sheet, on Standard 280001, and as directed by the Engineer.

The symbology on the STORM WATER POLLUTION PREVENTION PLAN sheets does not represent the size or quantity of bales, for number of bales refer to details and notes shown on this sheet and/or as directed by the Engineer.

THE CONTRACTOR SHALL INSTALL DITCH CHECKS AS DIRECTED BY THE ENGINEER. IF THE ENGINEER ELECTS TO UTILIZE FLUSH RIPRAP DITCH CHECKS IN LIEU OF TEMPORARY DITCH CHECKS AS SHOWN ON THE FOLLOWING PLAN SHEETS, THE SPACING SHOULD BE DOUBLED.

FILE NAME =	USER NAME = laughlinrl	DESIGNED	-		REVISED	-	AUG 2007	(JCN)
c:\pw_work\PWIDOT\LAUGHLINRL\dØ170829\D672B99-sht-erosion1.dgn			-	CADD	REVISED	-		
	PLOT SCALE = 40.000 '/ IN.	CHECKED	-	JCN	REVISED	-		
	PLOT DATE = 0ct-29-2009 11:54:54AM	DATE	-	APRIL 5, 1999	REVISED	-		

STATE OF	ILLINOIS
DEPARTMENT OF	TRANSPORTATION

STORM WATER POLLUTION PREVENTION PLAN						F.A.P. RTE.	SEC	COUNTY	TOTAL SHEETS	SHEET NO.	
						662	(2-1-2, 2-2	) RS, TS-6	SANGAMON	244	159
									CONTRACT	T NO. 7	2B99
	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. RO	DAD DIST. NO.	ILLINOIS FED. AI	D PROJECT		