

2. IMMEDIATELY UPON EXECUTION OF THE CONTRACT AND PRIOR TO THE WRECKING OF ANY STRUCTURES, THE CONTRACTOR SHALL BE REQUIRED TO PAINT OR STENCIL, IN CONTRASTING COLORS OF AN OIL BASE PAINT, ON ALL FOUR SIDES OF EACH RESIDENCE AND TWO OPPOSITE SIDES OF OTHER STRUCTURES, THE FOLLOWING SIGN:

3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR EACH PARCEL TO BE CLEAR OF ALL TREES, SHRUBBERY, AND LANDSCAPE ITEMS SUCH THAT THE PROPERTY CAN PRESENT A NEAT AND CLEAN APPEARANCE ON COMPLETION OF THIS PROJECT. THE CONTRACTOR WILL THEN BE REQUIRED TO REMOVE AND DISPOSE OF ALL TREES AND SHRUBS

4. CLEARING AND GRUBBING OF THE WEST PORTION OF THE SIDDLE PROPERTY WILL TAKE PLACE BY MACHINE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL SOIL FROM THE TREES, SHRUBS, ROOTS, AND LANDSCAPE ITEMS PRIOR TO THE BURNING OF MATERIAL. NO SOIL SHALL BE PRESENT ON ANY TREE, SHRUB, ROOT, OR LANDSCAPE ITEM TO BE BURNED.

5. FOR THE EAST PORTION OF THE SIDDLE PROPERTY THE CONTRACTOR SHALL BE REQUIRED TO CUT ALL TREES AND SHRUBS FLUSH WITH THE GROUND AND REMOVE BY HAND. ALL TREES AND SHRUBS SHALL BE CUT AT GROUND LEVEL. NO EXCAVATION IS TO BE MADE TO REMOVE THE ROOT SYSTEM. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL SOIL FROM THE TREES, SHRUBS, ROOTS, AND LANDSCAPE ITEMS PRIOR TO THE BURNING OF MATERIAL. NO SOIL SHALL BE PRESENT ON ANY TREE, SHRUB, ROOT, OR LANDSCAPE ITEM TO BE BURNED.

ONCE THE VEGETATION IS REMOVED IT 6. ONCE THE VEGETATION IS REMOVED IT SHALL BE PLACED ON AN EXISTING CONCRETE PAD AND CAN BE BURNED ON-SITE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN THE PROPER BURN PERMIT. ONCE THE VEGETATION IS BURNED, THE ASHES SHALL BE PLACED IN THE AREA OF THE CAP AND THEN COVERED BY THE CAP.

THE CONTRACTOR IS REQUIRED TO 7. THE CONTRACTOR IS REQUIRED TO OBTAIN AN OPEN BURNING PERMIT FROM THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY, AS WELL AS PROVIDE (2) COPIES OF THE APPROVED PERMIT TO THE CITY OF EAST ST. LOUIS FIRE DEPARTMENT AND DEPARTMENT OF REGULATORY AFFAIRS PRIOR TO ANY PURDING ON OBJECTE

8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING ALL MATERIALS, EQUIPMENT AND LABOR, AND PERFORMING THE REQUIRED OPERATIONS FOR THE CONTINUED WATERING OF THE ASPHALT SURFACES ALONG WITH THE OF THE ASPHALT SURFACES ALONG WITH THE GRAVEL AREAS WHICH ARE BEING USED BY THE CONTRACTOR. THIS WORK SHALL BE DONE ON A DAILY BASIS OR TO THE SATISFACTION OF THE ENGINEER TO PREVENT ANY LEAD FROM BECOMING AIRBORNE. SPECIAL ATTENTION SHOULD BE GIVEN AND ADDITIONAL WATERING BE DONE, TO ANY AREAS THAT ARE GRAVEL OR GRASS WHICH THE CONTRACTOR CHOOSES TO USE AS A STAGING AREA FOR THE DEMOLITION WORK.

9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR EACH PARCEL TO BE CLEAR OF ALL REAL PROPERTY, CHATTEL, DEBRIS AND ALL RUBBISH AND PRESENT A NEAT AND CLEAN APPEARANCE ON COMPLETION OF THIS PROJECT. THE CONTRACTOR WILL THEN BE REQUIRED TO REMOVE ALL MISCELLANEOUS DEFRIS AND RIBRISH.

TOTAL SHEE

