

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: I000

GENERAL NOTES

CODE NO.	ITEM	UNIT	TOTAL
* 1	31100900 SUB-BASE GRANULAR MATERIAL, TYPE A, 10"	SQ YD	311
* 2	40600100 BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,406
3	40600300 AGGREGATE (PRIME COAT)	TON	25
* 4	40600525 LEVELING BINDER (HAND METHOD), N50	TON	50
5	40600625 LEVELING BINDER (MACHINE METHOD), N50	TON	667
6	40600990 TEMPORARY RAMP	SQ YD	159
7	40603335 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,551
8	42400200 PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	773
9	42400800 DETECTABLE WARNINGS	SQ FT	102
* 10	44000154 HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	14,008
11	44000500 COMBINATION CURB AND GUTTER REMOVAL	FOOT	304
12	44000600 SIDEWALK REMOVAL	SQ FT	773
* 13	44212899 PAVEMENT PATCHING (FULL DEPTH)	SQ YD	311
* 14	44300300 AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	SQ YD	12,460
* 15	56109210 WATER VALVES TO BE ADJUSTED	EACH	4
* 16	60255500 MANHOLES TO BE ADJUSTED	EACH	27
* 17	60260100 INLETS TO BE ADJUSTED	EACH	29
* 18	60300105 FRAMES AND GRATES TO BE ADJUSTED	EACH	2
* 19	60610400 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	304
20	67100100 MOBILIZATION	L SUM	1
* 21	70101700 TRAFFIC CONTROL AND PROTECTION	L SUM	1
22	70300100 SHORT-TERM PAVEMENT MARKING	FOOT	1,041
23	70301000 WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	344
Δ 24	78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94
Δ 25	78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,406
Δ 26	78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,423
Δ 27	78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	153
* 28	81400115 HANDHOLE TO BE ADJUSTED	EACH	1

ALL BORROW/WASTE/USE SITES MUST BE APPROVED BY THE DEPARTMENT PRIOR TO REMOVING ANY MATERIAL FROM THE PROJECT OR INITIATING ANY EARTHMOVING ACTIVITIES, INCLUDING TEMPORARY STOCKPILING OUTSIDE THE LIMITS OF CONSTRUCTION.

MILLING MACHINES ON THIS PROJECT SHALL BE CAPABLE OF REMOVING A LAYER OF BITUMINOUS MATERIAL A MINIMUM OF 6' WIDE AND 1 1/4 INCHES IN DEPTH IN A SINGLE PASS. THE MAXIMUM DROP-OFF HEIGHT BETWEEN TRAVELED LANES SHALL BE EQUAL TO OR LESS THAN 1 1/4".

THE CONTRACTOR SHALL PLACE TEMPORARY HOT-MIX ASPHALT TAPERS ALONG ALL SIDES OF THE UTILITY STRUCTURES PROTRUDING ABOVE THE MILLED SURFACE. THE TEMPORARY TAPERS SHALL EXTEND 2' OUTSIDE OF THE CASTINGS, EXCEPT FOR THE APPROACH SIDE TO TRAFFIC, WHICH SHALL HAVE A 4' TAPER. HOT-MIX ASPHALT MEETING THE APPROVAL OF THE ENGINEER SHALL BE USED, AND NO COLD MILLINGS WILL BE ALLOWED. THE COST OF THE MATERIAL, PLACEMENT, MAINTENANCE, REMOVAL, AND DISPOSAL OF SAID WORK WILL BE INCLUDED IN THE PAY ITEM FOR "HOT-MIX ASPHALT SURFACE REMOVAL - 1 1/4".

THE AREA TO BE PRIMED SHALL BE LIMITED TO THAT WHICH CAN BE COVERED WITH HOT-MIX ASPHALT THE SAME DAY, UNLESS OTHERWISE PERMITTED BY THE ENGINEER.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE "JULIE" NUMBER IS 800-892-0123. THE UTILITIES LOCATED WITHIN THE PROJECT LIMITS, OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS, ARE MEMBERS OF "JULIE" AND ARE LISTED ON THE COVER SHEET OF THESE PLANS.

UTILIZATION OF THE PAY ITEMS "LEVELING BINDER (HAND METHOD)", "PAVEMENT PATCHING (FULL DEPTH)", AND "SUB-BASE GRANULAR MATERIAL, TYPE A, 10'" SHALL BE AT THE DISCRETION OF THE RESIDENT ENGINEER. A CONTINGENCY AMOUNT FOR EACH ITEM HAS BEEN PLACED IN THIS CONTRACT.

* INDICATES SPECIAL PROVISION

Δ SPECIALTY ITEMS



DESIGNED - BDF	REVISED -
DRAWN - BDF	REVISED -
CHECKED - BDF	REVISED -
DATE - 08/17/2009	REVISED -

CITY OF ROCK FALLS, ILLINOIS
12th AVENUE - ROCK RIVER BRIDGE to W. 10th ST.

SUMMARY OF QUANTITIES GENERAL NOTES

SCALE:

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	09-00130-00-RS	WHITESIDE	21	2
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT			CONTRACT NO. 85499	