



LEGEND	
	TEMPORARY DITCH CHECK @ 50' SPACING
	PERIMETER EROSION BARRIER
	TEMPORARY EROSION CONTROL SEEDING, HEAVY DUTY EROSION CONTROL BLANKET & SEEDING, CLASS 2 (SPECIAL)
	STONE RIPRAP, CLASS A5
	DECIDUOUS TREE TO BE REMOVED

- NOTES:**
- 1.) ALL SEDIMENT AND EROSION CONTROL SYSTEMS SHALL BE CONSTRUCTED WITHIN THE RIGHT-OF-WAY OR TEMPORARY EASEMENT.
 - 2.) ALL SEDIMENT AND EROSION CONTROL SYSTEMS SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EACH 1/2" OR GREATER RAIN EVENT.

DESIGNED - JML	REVISED -
DRAWN - DJM	REVISED -
CHECKED - MSW	REVISED -
DATE - 10/21/09	REVISED -

LIVINGSTON COUNTY DEPARTMENT OF HIGHWAYS

EROSION CONTROL PLAN

SCALE: SHEET NO. 10 OF 34 SHEETS STA. TO STA.

WESTON ROAD (C.H. 10) OVER HICKORY CREEK
SECTION 09-00120-03-BR
LIVINGSTON, COUNTY

F.A.S.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	09-00120-03-BR	LIVINGSTON	34	10
S.N. 053-5015		CONTRACT NO. 07412		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		