PAVEMENT SCHEDULE

STATION TO STATION	WIDTH	LENGTH	PRIME COAT GALLON 0.10 GAL/SQ YD	LEVELING BINDER (MACHINE METHOD) TON 112#/SQ YD/IN	HOT-MIX ASPHALT SURF CSE TON 112#/SQ YD/IN	HOT-MIX ASPHALT SURF REMOVAL, VARIABLE DEPTH SQ YD	BRIDGE APPROACH PAVEMENT SQ YD	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) SQ YD
36+50.00 - 37+50.00	24.17' AVG.	100.00'	27					
37+50.00 - 39+27.42	24.00'	177.42'	47					
40+74.42 - 43+25.00	24.00'	250.58'	67					
43+25.00 - 45+00.00	24.17' AVG.	175.00'	47					
37+25.00 - 39+21.42	24.00'	196.42'		106				
40+80.42 - 43+50.00	24.00'	269.58'		86				
36+50.00 - 37+50.00	24.27' AVG.	100.00'			23			
37+50.00 - 39+21.42	24.13'	171.42'			39			
40+80.42 - 43+25.00	24.13'	244.58'			55			
43+25.00 - 45+00.00	24.27' AVG.	175.00'			40			
36+50.00 - 37+50.00	24.17' AVG.	100.00'				269		
43+25.00 - 45+00.00	24.17' AVG.	175.00'				470		
39+27.42 - 39+57.42	37.00'	30.00'					123	
40+44.42 - 40+74.42	37.00'	30.00'					124	
39+21.42 - 39+27.42	37.00'	6.00'						25
40+74.42 - 40+80.42	37.00'	6.00'						25
		TOTAL	188	192	157	739	247	50

AGGREGATE SHOULDERS, TYPE B 6"

STATION TO STATION	SIDE	WIDTH	LENGTH	TON
36+50.00 - 37+00.00	LEFT	5.40' AVG.	50.00'	9
36+50.00 - 37+00.00	RIGHT	5.60' AVG.	50.00'	10
37+00.00 - 38+40.65	LEFT	8.00'	140.65'	39
37+00.00 - 38+40.65	RIGHT	8.00'	140.65'	39
38+40.65 - 38+53.67	LEFT	9.09' AVG.	13.02'	4
38+40.65 - 38+53.67	RIGHT	9.09' AVG.	13.02'	4
38+53.67 - 38+88.67	LEFT	10.17'	35.00'	12
38+53.67 - 38+88.67	RIGHT	10.17'	35.00'	12
38+88.67 - 38+92.69	LEFT	9.84' AVG.	4.02'	1
38+88.67 - 38+92.69	RIGHT	9.84' AVG.	4.02'	1
38+92.69 - 39+21.42	LEFT	9.50'	28.73'	10
38+92.69 - 39+21.42	RIGHT	9.50'	28.73'	10
39+21.42 - 39+49.92	LEFT	3.00'	28.50'	3
39+21.42 - 39+49.92	RIGHT	3.00'	28.50'	3
39+49.92 - 39+57.42	LEFT	2.75' AVG.	7.50'	1
39+49.92 - 39+57.42	RIGHT	2.75' AVG.	7.50'	1
40+44.42 - 40+51.92	LEFT	2.75' AVG.	7.50'	1
40+44.42 - 40+51.92	RIGHT	2.75' AVG.	7.50'	1
40+51.92 - 40+80.42	LEFT	3.00'	28.50'	3
40+51.92 - 40+80.42	RIGHT	3.00'	28.50'	3
40+80.42 - 40+09.15	LEFT	9.50'	28.73'	10
40+80.42 - 40+09.15	RIGHT	9.50'	28.73'	10
40+09.15 - 41+13.17	LEFT	9.84' AVG.	4.02'	1
40+09.15 - 41+13.17	RIGHT	9.84' AVG.	4.02'	1
41+13.17 - 41+48.17	LEFT	10.17'	35.00'	12
41+13.17 - 41+48.17	RIGHT	10.17'	35.00'	12
41+48.17 - 41+61.19	LEFT	9.09' AVG.	13.02'	4
41+48.17 - 41+61.19	RIGHT	9.09' AVG.	13.02'	4
41+61.19 - 44+50.00	LEFT	8.00'	288.81'	81
41+61.19 - 44+50.00	RIGHT	8.00'	288.81'	81
44+50.00 - 45+00.00	LEFT	5.80' AVG.	50.00'	10
44+50.00 - 45+00.00	RIGHT	5.98' AVG.	50.00'	10
			TOTAL	403

AGGREGATE DITCH**

STATION TO STATION	SIDE	WIDTH	TON	FILTER FABRIC (SQ YD)
39+33.00 - 39+53.00	LT	8'	9	18
39+43.00	RT	6'	8	16
40+44.00 - 41+41.00	RT	8'	45	87
41+81.00 - 42+00.00	RT	8'	9	17
		TOTAL	71	138

** AGGREGATE DITCH SHALL CONFORM TO MATERIAL TYPE A-4 OF THE STANDARD SPECIFICATIONS.

TEMPORARY DITCH CHECKS

STATION	SIDE	FOOT
40+25	RIGHT	11
40+38	RIGHT	11
40+51	RIGHT	11
40+64	RIGHT	11
40+77	RIGHT	11
40+90	RIGHT	11
41+03	RIGHT	11
41+16	RIGHT	11
41+29	RIGHT	11
	TOTAL	99

PERIMETER EROSION BARRIER

STATION TO STATION	SIDE	FOOT
36+50 - 39+57	LEFT	345
36+50 - 39+57	RIGHT	355
40+44 - 45+00	LEFT	490
41+41 - 41+81	RIGHT	45
42+00 - 45+00	RIGHT	305
	TOTAL	1,540

PAVEMENT REMOVAL

STATION TO STATION	LENGTH	WIDTH	SQ YD
39+21.42 - 39+73.51	52.09'	24'	139
40+26.29 - 40+80.42	54.13'	24'	144
		TOTAL	283

INLET FILTERS

STATION	SIDE	EACH
39+43	RIGHT	1
39+43	LEFT	1
	TOTAL	2

PAVED DITCH REMOVAL

STATION TO STATION	SIDE	FOOT
39+54 - 39+82	LEFT	28
40+24 - 41+44	RIGHT	120
	TOTAL	148

AGGREGATE SURFACE COURSE, TYPE B

STATION	TYPE	TON
41+61	FE	37
	TOTAL	37

GUARDRAIL REMOVAL

STATION TO STATION	SIDE	FOOT
38+67 - 39+71	LEFT	104
38+67 - 39+71	RIGHT	104
40+29 - 41+33	LEFT	104
40+29 - 41+33	RIGHT	104
	TOTAL	416

INLET & PIPE PROTECTION

STATION	SIDE	EACH
41+81	RIGHT	1
	TOTAL	1

PIPE CULVERT REMOVAL

STATION	SIDE	FOOT
41+61	RT	38
	TOTAL	38

CLASS B PATCHES, TYPE II, 10 INCH

STATION TO STATION	SIDE	SQ YD
39+12 - 39+21	LEFT	13
	TOTAL	13