INDEX OF SHEETS

SHEET NO. DESCRIPTION COVER SHEET GENERAL NOTES, DETAILS, 2. TYPICAL SECTIONS SUMMARY OF QUANTITIES, SCHEDULES OF QUANTITIES TRAFFIC CONTROL PLAN EROSION CONTROL PLAN PLAN AND PROFILE 6. STRUCTURE PLANS 7. -16. 17. -21. CROSS SECTIONS

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION PLANS FOR PROPOSED **HIGHWAY BRIDGE PROGRAM MASON COUNTY** SECTION 07-00032-01-BR F.A.S. 568 (CH 3) OVER QUIVER CREEK PROJECT NO. BRS-0568(102) JOB NUMBER C-96-215-10

REQUIRED HIGHWAY STANDARDS PROFILE HORIZ. 000001-05 280001-05 PROFILE VERT. 515001-03 630301-05 CROSS SECTIONS HORIZ. 635006-03 CROSS SECTIONS VERT. 701901-01 BLR 21-8 BLR 26-2 BLR 27-1 SECTION 07-00032-01-BR ENDS STATION 21+75.00 PROPOSED STRUCTURE NO. 063-3011 THREE SPAN 17" & 33" P.P.C. DECK BEAM STRUCTURE ON CONCRETE SPILL THRU PILE BENT ABUTMENTS AND CONCRETE ENCASED PIERS, 145'-0" BK. TO BK. AND 30'-0" O. TO O., EXISTING STRUCTURE 063-3010 THREE SPAN REINFORCED CONCRETE DECK ON STEEL STRINGERS SUPERSTRUCTURE ON SECTION 07-00032-01-BR BEGINS STATION 18+25.00 AND CONCRETE PILE BENT PIERS, 135'-0" BK. TO BK., AND 27'-8" O. TO O., NO SKEW (TO BE REMOVED) R. 7 W. 3rd P.M.

SPILL THRU CONCRETE PILE BENT ABUTMENTS

UTILITY COMPANIES

AMEREN CIPS BEARDSTOWN, ILLINOIS

CENTURYTEL PEKIN, ILLINOIS

J.U.L.I.E. JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123 OR 811

CONTRACT NO. 93505

NET LENGTH OF PROJECT = 350.00 FEET = 0.066 MILES

LOCATION MAP

APPROXIMATE SCALE

DESIGN CLASSIFICATION: MAJOR-COLLECTOR (NON-URBAN) DESIGN ADT = 175 (2009) DESIGN SPEED = 40 MPH

Hutchison Engineering, Inc. JACKSONVILLE ILLINOIS

SIGNATURE ENGINEERS SEAL

07-00032-01-BR MASON 21 1 FED. ROAD DIST. NO. 7 ILLINOIS CONTRACT NO. 9 3 5 0



	APPROVED OCT 6TE	2009
	MASON COUNTY ENGINEER	
	PASSED OCTOBER 26	2009
	DISTRICT SIX ENGINEER OF LOCAL ROADS & STREETS	
	PASSED October 26	2009
>	DISTRICT SIX ENGINEER	:
	OF CONSTRUCTION Released For Bid Based on Limited Review OCTOBER ZG Roger & Duskell not	2009
49	DEPUTY DIRECTOR OF HIGHWAYS, REGION FOUR ENGINEER	
_	STATE OF ILLINOIS	

DEPARTMENT OF TRANSPORTATION