

MODEL: Default
FILE NAME: prj\planroom dot illinois gov\PWDOT\Documents\DOT Office\District 8\Project\0672196\CAD\data\CAD\sheet\0672196-ht-500.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	6-01457-0000
				80% FEDERAL
				20% STATE
				BRIDGE
				0059
				URBAN
				054-0104
28100205	STONE RIPRAP, CLASS A3	TON	20	20
35501314	HOT-MIX ASPHALT BASE COURSE, 7 1/2"	SQ YD	196	196
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	217	217
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	529	529
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	31	31
40600990	TEMPORARY RAMP	SQ YD	69	69
40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	52	52
42001300	PROTECTIVE COAT	SQ YD	1545	1545
44004250	PAVED SHOULDER REMOVAL	SQ YD	196	196
48203100	HOT-MIX ASPHALT SHOULDERS	TON	16.5	16.5
50300260	BRIDGE DECK GROOVING	SQ YD	1451	1451
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	6-01457-0000
				80% FEDERAL
				20% STATE
				BRIDGE
				0059
				URBAN
				054-0104
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	30	30
* 78009005	MODIFIED URETHANE PAVEMENT MARKING - LINE 5"	FOOT	4870	4870
X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	469	469
X6026100	INLETS TO BE RECONSTRUCTED WITH NEW FRAME AND GRATE, SPECIAL	EACH	2	2
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1
Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	1545	1545
Z0012164	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	1545	1545
Z0018051	DRAINAGE SCUPPERS TO BE ADJUSTED	EACH	2	2
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	10	10
Ø Z0076600	TRAINEES	HOURL	500	500
Z0041895	POLYMER CONCRETE	CU FT	8.5	8.5
Ø Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURL	500	500
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

* SPECIALTY ITEM

Ø 0042

△ REV. 1-5-2021

REV. - MS

	USER NAME = COXJW	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES FAU 7706 (LINCOLN PKWY)		F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -				7706	22(BDR)	LOGAN	24	3
	PLOT SCALE = 100.0008 ' / in.	CHECKED -	REVISED +				CONTRACT NO. 72L96				
	PLOT DATE = 10/16/2020	DATE -	REVISED +				ILLINOIS FED. AID PROJECT				
SCALE:		SHEET	OF	SHEETS	STA.	TO STA.					