



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 5, 2021

SUBJECT: Route FAU 5112 (Seminary Street)  
Section 19-00630-00-BR (Rockford)  
Winnebago County  
Contract No. 85703  
Item 152  
January 15, 2021 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices.**
- 2. Revised sheet 3 of the Plans.**
- 3. Revised page 10 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

within 14 days from when activities ceased, (e.g. the total time period that construction activity is temporarily ceased is less than 14 days) then stabilization measures do not have to be initiated on that portion of the site by the 14th day after construction activity temporarily ceased. Best management practices will be in place downslope of the disturbed areas until final stabilization has occurred.

Any excess construction materials on site must be properly disposed of. All excess concrete material must be disposed of in an approved concrete washout container. NO CONCRETE IS TO BE WASHED INTO THE PARKWAY. The type, size, location and design of the concrete washout structures may vary but each must be approved prior to use.

When excess topsoil and excavated material is removed from the site, the Contractor shall take special precautions to avoid tracking or spilling dirt onto the adjacent roadways. If excavated material is spilled outside of the job site, the Contractor shall remove the debris and clean the pavements to the satisfaction of the Engineer, and properly dispose of the material.

**DISPOSAL OF CLEAN CONSTRUCTION AND DEMOLITION DEBRIS (CCDD).**

- NON-SPECIAL WASTE DISPOSAL (IDOT PAY ITEM 66900200)
- REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN (IDOT PAY ITEM 66901001)
- REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT (IDOT PAY ITEM 66901003)
- SOIL DISPOSAL ANALYSIS (IDOT PAY ITEM 66900530)
- ON-SITE MONITORING OF REGULATED SUBSTANCES (IDOT PAY ITEM 66901006)

See Brownfield Environmental Engineering report for additional information on page 85.

Per guidelines set by the Illinois Environmental Protection Agency (IEPA) (Public Act 96-1416, effective July 30, 2010) construction and disposal practices at jobsites and at CCDD sites have been changed as of July 30, 2010.

As stated by the IEPA: "Clean Construction and Demolition Debris (CCDD) is uncontaminated broken concrete without protruding metal bars, bricks, rock, stone, or reclaimed asphalt pavement generated from construction or demolition activities. When uncontaminated soil is mixed with any of these materials, the uncontaminated soil is also considered CCDD. Uncontaminated soil that is not mixed with other CCDD materials is not CCDD."

Under this contract, material to be removed from the jobsite shall be disposed of at the Contractor's expense following all applicable local, state and federal requirements as well as any requirements set forth by the Illinois Environmental Protection Agency and the Illinois State Pollution Control Board. These legal requirements specifically include but are not limited to the Illinois Environmental Protection Act (415 ILCS 5), IEPA CCDD Guidelines (Public Act 96-1416), and Title 35 of the Illinois Administrative Code.

It shall be the Contractor's responsibility to properly dispose of all material to be removed from the project limits including both CCDD and non CCDD material. Any additional costs incurred to the Contractor for the disposal of material shall be considered incidental to various excavation and removal pay items and will not be considered for additional payment of any kind. Such additional incidental costs may specifically include but are not limited to trucking and hauling, off-site material handling, over-weight permits, tipping fees, regulatory fees and surcharges, any applicable taxes, and any disposal costs including those for hazardous and non-hazardous special waste. No special pay item for Non-Special Waste Removal, Special Waste Removal, or Hazardous Waste Removal has been included in this contract, but the requirements for removal of such materials must still be in accordance with Articles 202 and 669 of the Standard Specifications for Road and Bridge Construction.