

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	2020-093-1	COOK	18	1
ILLINOIS			CONTRACT NO. 62L71	

* 18 + 1 = 19 TOTAL SHEETS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

01-15-2021 LETTING ITEM 171

FOR INDEX OF SHEETS, SEE SHEET NO. 2

PROJECT LOCATED IN
THE CITY OF CHICAGO,
VILLAGE OF HARWOOD HEIGHTS
AND VILLAGE OF NORRIDGE

PROPOSED
HIGHWAY PLANS


F.A.P. ROUTE 348: IL 43 (HARLEM AVENUE)
IL 72 (HIGGINS ROAD) TO SOUTH OF CULLOM AVENUE
SECTION: 2020-093-1

CRACK & JOINT SEALING
COOK COUNTY

C-91-290-20




TRAFFIC DATA
ADT 2019: 29400 VPD
SPEED LIMIT: 30 MPH



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION
1-800-892-0123
OR 811

PROJECT BEGINS:
STA. 10 + 37



PROJECT ENDS:
STA. 99 + 58

GROSS LENGTH = 8921 FT. = 1.69 MILE
NET LENGTH = 8921 FT. = 1.69 MILE

PROJECT ENGINEER: DANIEL WILGREEN (847) 705-4240
PROJECT MANAGER: FAWAD AQUEEL (847) 705-4247

CONTRACT NO. 62L71

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUBMITTED June 28, 2020

[Signature]
REGIONAL ENGINEER

October 2, 2020

[Signature]
ENGINEER OF DESIGN AND ENVIRONMENT

October 2, 2020

[Signature]
DIRECTOR OF HIGHWAYS PROJECT IMPLEMENTATION

PRINTED BY THE AUTHORITY
OF THE STATE OF ILLINOIS

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES
3-4	SUMMARY OF QUANTITIES
5-6	TYPICAL SECTIONS
7-10	ROADWAY PLANS AND PAVEMENT MARKING PLANS
10A	CRACK & JOINT SEALING DETAIL
11	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT (BD-24)
12	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)
13	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)
14	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) (TC-14)
15	ARTERIAL ROAD INFORMATION SIGNING (TC-22)
16-18	CITY OF CHICAGO TYPICAL PAVEMENT MARKINGS (TC-24)

STANDARDS

442101-09	CLASS B PATCHES
701006-05	OFF-RD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701101-05	OFF ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701311-03	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
701427-05	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS, FOR SPEEDS < 40 MPH
701602-10	URBAN LANE CLOSURE, MULTILANE, 2W WITH BY-DIRECTIONAL LEFT TURN LANE
701606-10	URBAN SINGLE LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-10	URBAN SINGLE LANE CLOSURE, MULTILANE INTERSECTION
701801-06	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-08	TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E". AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES OF THE CITY OF CHICAGO, VILLAGE OF HARWOOD HEIGHTS AND VILLAGE OF NORRIDGE.

ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT NO ADDITIONAL COST TO THE DEPARTMENT.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR VIA EMAIL Kalpana.Kannan-Hosadurga@illinois.gov (FOR ARTERIALS) A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE ENGINEER SHALL CONTACT EMAD ALHUSSEINI AREA TRAFFIC FIELD ENGINEER AT EMAD.ALHUSSEINI@ILLINOIS.GOV A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

MODIFIED URETHANE PAVEMENT MARKING SHALL BE PLACED IMMEDIATELY AFTER C & J SEALER TEMPERATURE HAS COOLED DOWN AND DOES NOT AFFECT THE APPLICATION OF MODIFIED URETHANE PAVEMENT MARKING

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**


**INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES
IL43 (HARLEM AVE.) (IL RTE. 72 - CULLOM AVE.)**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	2020-093-I	COOK	18	2
			CONTRACT NO. 62L71	
		ILLINOIS	FED. AID PROJECT	


SCALE: SHEET OF SHEETS STA. TO STA.

LEGEND

- ① EXISTING PORTLAND CEMENT CONCRETE PAVEMENT - 9 3/4"
- ② EXISTING CURB AND GUTTER
- ③ EXISTING CONCRETE MEDIAN



**TYPICAL SECTION
WITH PAINTED MEDIAN
AND TURNING LANE**



**TYPICAL SECTION
WITH PAINTED MEDIAN
AND TURNING LANE**


MODEL: Default
 FILE: \\harc...
 PROJECT: ...
 USER: mesadoj

USER NAME = mesadoj	DESIGNED -	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN -	REVISED -
PLOT DATE = 8/14/2020	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**


EXISTING ROADWAY CROSS SECTIONS			
IL 43 (HARLEM AVENUE) (IL. RTE. 72 - CULLOM AVE.)			
SCALE:	SHEET	OF SHEETS	STA. TO STA.

F.A.P. RTE. 348	SECTION 2019-093-I	COUNTY COOK	TOTAL SHEETS 18	SHEET NO. 6
CONTRACT NO. 62L71				
ILLINOIS FED. AID PROJECT				



PAVEMENT MARKING LEGEND:

- ① 4" MODIFIED URETHANE DOUBLE SOLID YELLOW LINE
2 @ 11" C-C (TYP.)
- ② 4" MODIFIED URETHANE SOLID YELLOW LINE
- ③ 4" MODIFIED URETHANE SOLID WHITE LINE (TYP.)
- ④ 4" MODIFIED URETHANE SKIP-DASH WHITE LINE
10' DASH - 30' SKIP (TYP.)
- ⑤ 6" MODIFIED URETHANE SOLID WHITE TURN LANE LINE (TYP.)
- ⑥ 6" MODIFIED URETHANE SOLID WHITE CROSSWALK LINE (TYP.)
- ⑦ 6" MODIFIED URETHANE SKIP-DASH WHITE LINE
2' DASH - 6' SKIP (TYP.)
- ⑧ 24" MODIFIED URETHANE SOLID WHITE STOP BAR (TYP.)
- ⑨ MODIFIED URETHANE, LETTERS & SYMBOLS, SOLID WHITE (TYP.)
- ⑩ 12" MODIFIED URETHANE SOLID YELLOW LINE, 20' C-C @ 45 DEG.
- ⑪ 12" MODIFIED URETHANE SOLID WHITE CROSSWALK (TC13, TC24)
- ⑫ 8" SOLID WHITE GORE MARKING AND CHANNELIZING LINES
12" DIAGONALS, 30' C-C @ 45 DEG.




MODEL: Default
 FILE: h:\mfc_pav\pub\harcross.dwg
 PROJECT: I:\Projects\149220\CADD\Drawings\149220-sh-c-lb.dwg

USER NAME = mesadoj	DESIGNED -	REVISED -
PLOT SCALE = 100.0000' / in.	DRAWN -	REVISED -
PLOT DATE = 8/14/2020	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


ROADWAY PLANS AND PAVEMENT MARKING PLANS
IL. RTE. 43 (HARLEM AVE.) (IL. RTE. 72 - CULLOM AVE.)
 SCALE: 1"=50' SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	2019-093-I	COOK	18	8
CONTRACT NO. 62L71				
ILLINOIS FED. AID PROJECT				



PAVEMENT MARKING LEGEND:

- ① 4" MODIFIED URETHANE DOUBLE SOLID YELLOW LINE
2 @ 11" C-C (TYP.)
- ② 4" MODIFIED URETHANE SOLID YELLOW LINE
- ③ 4" MODIFIED URETHANE SOLID WHITE LINE (TYP.)
- ④ 4" MODIFIED URETHANE SKIP-DASH WHITE LINE
10' DASH - 30' SKIP (TYP.)
- ⑤ 6" MODIFIED URETHANE SOLID WHITE TURN LANE LINE (TYP.)
- ⑥ 6" MODIFIED URETHANE SOLID WHITE CROSSWALK LINE (TYP.)
- ⑦ 6" MODIFIED URETHANE SKIP-DASH WHITE LINE
2' DASH - 6' SKIP (TYP.)
- ⑧ 24" MODIFIED URETHANE SOLID WHITE STOP BAR (TYP.)
- ⑨ MODIFIED URETHANE, LETTERS & SYMBOLS, SOLID WHITE (TYP.)
- ⑩ 12" MODIFIED URETHANE SOLID YELLOW LINE, 20' C-C @ 45 DEG.
- ⑪ 12" MODIFIED URETHANE SOLID WHITE CROSSWALK (TC13, TC24)
- ⑫ 8" SOLID WHITE GORE MARKING AND CHANNELIZING LINES
12" DIAGONALS, 30' C-C @ 45 DEG.




MODEL: Default
 FILE: \\baron.com\data\illinois.gov\pww\DOT\Documents\DOT_Offices\District 1\Projects\149220\CADD\Drawings\149220-sh-4-bar.dgn

USER NAME = mesadoj	DESIGNED -	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN -	REVISED -
PLOT DATE = 8/14/2020	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROADWAY PLANS AND PAVEMENT MARKING PLANS
IL. RTE. 43 (HARLEM AVE.) (IL. RTE. 72 - CULLOM AVE.)
 SCALE: 1"=50' SHEET OF SHEETS STA. TO STA.

F.A.P. RTE. 348	SECTION 2019-093-I	COUNTY COOK	TOTAL SHEETS 18	SHEET NO. 9
CONTRACT NO. 62L71				
ILLINOIS FED. AID PROJECT				



PAVEMENT MARKING LEGEND:

- ① 4" MODIFIED URETHANE DOUBLE SOLID YELLOW LINE
2 @ 11" C-C (TYP.)
- ② 4" MODIFIED URETHANE SOLID YELLOW LINE
- ③ 4" MODIFIED URETHANE SOLID WHITE LINE (TYP.)
- ④ 4" MODIFIED URETHANE SKIP-DASH WHITE LINE
10' DASH - 30' SKIP (TYP.)
- ⑤ 6" MODIFIED URETHANE SOLID WHITE TURN LANE LINE (TYP.)
- ⑥ 6" MODIFIED URETHANE SOLID WHITE CROSSWALK LINE (TYP.)
- ⑦ 6" MODIFIED URETHANE SKIP-DASH WHITE LINE
2' DASH - 6' SKIP (TYP.)
- ⑧ 24" MODIFIED URETHANE SOLID WHITE STOP BAR (TYP.)
- ⑨ MODIFIED URETHANE, LETTERS & SYMBOLS, SOLID WHITE (TYP.)
- ⑩ 12" MODIFIED URETHANE SOLID YELLOW LINE, 20' C-C @ 45 DEG.
- ⑪ 12" MODIFIED URETHANE SOLID WHITE CROSSWALK (TC13, TC24)
- ⑫ 8" SOLID WHITE GORE MARKING AND CHANNELIZING LINES
12" DIAGONALS, 30' C-C @ 45 DEG.


MODEL: Default
 FILE: \\blm1c:\pub\blmroom\dat\illinois.gov\PWIDOT\Documents\DOT_Offices\blm1c\1\Projects\149220\CaddData\Design\149220-sh-4-lan.dgn

USER NAME = mesadoj	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 8/14/2020	DATE -	REVISED -


**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

ROADWAY PLANS AND PAVEMENT MARKING PLANS			
IL. RTE. 43 (HARLEM AVE.) (IL. RTE. 72 - CULLOM AVE.)			
SCALE: 1"=50'	SHEET	OF	SHEETS
	STA.	TO	STA.


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	2019-093-I	COOK	18	10
CONTRACT NO. 62L71				
ILLINOIS FED. AID PROJECT				



MULTI-LANE DIVIDED PAVEMENT




MULTI-LANE UNDIVIDED PAVEMENT




TWO-LANE PAVEMENT

* PROPOSED LONGITUDINAL CRACK ROUTING (PAVEMENT) & CRACK FILLING LOCATIONS

**GENERAL EXISTING TYPICAL SECTIONS
(APPLIES TO HMA AND PCC PAVEMENTS)**



* IN ALL LOCATIONS WHERE THE LONGITUDINAL CRACK CONFLICTS WITH EXISTING PAVEMENT MARKINGS (EITHER EDGE LINE OR LANE LINE) THE CRACK SHALL BE ROUTED & THE RESULTING RESERVOIR FILLED WITH SEALANT. ALL DAMAGES TO EXISTING RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR. ALL EXISTING PAVEMENT MARKINGS WITHIN THE PROJECT LIMITS SHALL BE RESTORED WITH MODIFIED URETHANE PAVEMENT MARKINGS.



CRACK & JOINT SEALING DETAIL

MODEL: D:\dault... FILE NAME: ...


USER NAME = leysa	DESIGNED - F. Aqueel / A. Midy	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 10/7/2020	DATE = 10/08/2020	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

CRACK & JOINT SEALING DETAIL (PD-11)

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE. 348	SECTION 2020-093-1	COUNTY COOK	TOTAL SHEETS 18	SHEET NO. 10A
CONTRACT NO. 62L71				
ILLINOIS FED. AID PROJECT				



NOTES:

1. SIDE ROAD WITH A SPEED LIMIT OF 40 MPH (60 km/h) OR LESS AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
 - a) ONE "ROAD CONSTRUCTION AHEAD" SIGN 36 x 36 (900x900) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 200' (60 m) IN ADVANCE OF THE MAIN ROUTE.
 - b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE I, TYPE II OR TYPE III BARRICADES, 1/3 OF THE CROSS SECTION OF THE CLOSED PORTION.
2. SIDE ROAD WITH A SPEED LIMIT GREATER THAN 40 MPH (60 km/h) AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
 - a) ONE "ROAD CONSTRUCTION AHEAD" SIGN 48 x 48 (1.2 m x 1.2 m) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 500' (150 m) IN ADVANCE OF THE MAIN ROUTE.
 - b) BLOCKING WITH TYPE III BARRICADES, 1/2 OF THE CROSS SECTION OF THE CLOSED PORTION.
3. CONES MAY BE SUBSTITUTED FOR BARRICADES OR DRUMS AT HALF THE SPACING DURING DAY OPERATIONS. CONES SHALL BE A MINIMUM OF 28 (710) IN HEIGHT.
4. SIGNING AND THE WORK ZONE, A SINGLE HEADED ARROW (M6-1) SHALL BE USED IN LIEU OF THE DOUBLE HEADED ARROW (M6-4).
5. WHEN WORK IS BEING PERFORMED ON A SIDE ROAD OR DRIVEWAY, FOLLOW THE APPLICABLE STANDARD(S). THE DIRECTIONAL ARROW (M6-1 OR M6-4) SHALL BE COVERED OR REMOVED WHEN NO LONGER CONSISTENT WITH THE TRAFFIC CONTROL SET-UP.
6. ADVANCE WARNING SIGNS ARE TO BE OMITTED ON DRIVEWAYS UNLESS OTHERWISE SPECIFIED IN THE PLANS OR BY THE ENGINEER.
7. THE TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

All dimensions are in inches (millimeters) unless otherwise shown.

MODEL: Default
 FILE: \\nas101.psu.edu\pub\room\data\illinois.gov\PWIDOT\Documents\DOT_Offices\Director_1\Projects\149220\CADD\Drawings\Design\DESIGN.dgn


USER NAME = mesadoj	DESIGNED - L.H.A.	REVISED - A. HOUSEH 10-15-96
	DRAWN -	REVISED - T. RAMMACHER 01-06-00
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED - A. SCHUETZE 07-01-13
PLOT DATE = 8/14/2020	DATE - 06-89	REVISED - A. SCHUETZE 09-15-16

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TRAFFIC CONTROL AND PROTECTION FOR
SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS**

SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	2020-093-I	COOK	18	12
TC-10			CONTRACT NO. 62L71	
ILLINOIS FED. AID PROJECT				



NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

MODEL: Default
 FILE: \\nls-px1\pub\ancom\dat\illinois.gov\PWIDOT\Documents\DOT_Offices\Dir\ctc_1\Project\210\CADData\Design\DRS\4.dgn

USER NAME = mesadoj	DESIGNED -	REVISED - R. MIRS 09-15-97
	DRAWN -	REVISED - R. MIRS 12-11-97
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED - T. RAMMACHER 02-02-99
PLOT DATE = 8/14/2020	DATE -	REVISED - C. JUCIUS 01-31-07


**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ARTERIAL ROAD
INFORMATION SIGN**

SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	2020-093-I	COOK	18	15
TC-22			CONTRACT NO. 62L71	
ILLINOIS FED. AID PROJECT				

MODEL: Default
 FILE: Model: 348\planroom.ctb\Illinois.gov\PWIDOT\Documents\DOT_Offices\District_1\Projects\149220\CADD\Drawings\Design\DES4.dgn



USER NAME = mesadoj	DESIGNED -	REVISED - T. RAMMACHER 12-07-00
	DRAWN -	REVISED -
PLOT SCALE = 100,0001' / in.	CHECKED -	REVISED -
PLOT DATE = 8/14/2020	DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**CITY OF CHICAGO
 TYPICAL PAVEMENT MARKINGS**

SCALE: NONE SHEET 3 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	2020-093-I	COOK	18	18
TC-24			CONTRACT NO. 62L71	
ILLINOIS FED. AID PROJECT				