


C SLOPE ENTRY FILLING DETAIL SIDE VIEW NOT TO SCALE 20' MAJOR RADIUS 10' MINOR RADIUS - SOIL COVER 3' MINIMUM (98 C.Y.) - FILTER FABRIC (42 S.Y.) -2' CA-6 FILL (46 TONS) -2' CA-1 FILL (24 TONS) SLOPE ENTRY -EXISTING GRADE APPROXIMATELY 10' x 5' -RIPRAP FILL C-3 (23 TONS) 8" PVC PIPE WITH MINIMUM OF 3' OF A COVER OVER IT. SPECIAL EXCAVATION LIMITS (140 C.Y.)

NOTE:
DUE TO THE UNKNOWN CONDITIONS THAT EXIST IN AND AROUND THE MINE OPENINGS, THE CONTRACTOR SHALL USE EXTREME CAUTION WHEN PERFORMING WORK NEAR THEM. THE ENGINEER RESERVES THE RIGHT TO INCREASE OR DECREASE THE QUANTITY FOR SPECIAL EXCAVATION AND BACKFILLING MATERIALS AS DETERMINED BY THE EXACT CONDITIONS ENCOUNTERED DURING SPECIAL EXCAVATION.



State of Illinois Department of Natural Resources

Main Guy Mine Reclamation Project AML-GScE-0806 St. Clair County

Date: 11/6/2008	12/3/08		
Drawn By: M-LF, V.P.	Checked By: +/n		

Detail Sheet Sheet 5 of 5