INDEX OF SHEETS

DESCRIPTION
COVER SHEET
INDEX OF SHEETS, STANDARDS, AND GENERAL NOTES
SUMMARY OF QUANTITIES
TRAFFIC STAGING
TYPICAL CONSTRUCTION SECTION
ROADWAY RESURFACING AND APPROACH OVERLAY PLAN
BRIDGE REPAIR PLAN SHEETS
MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS
TRAFFIC CONTROL DETAILS FOR FREEWAY SINGLE & MULTI-LANE WEAVE - TC-9
TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES - TC-17

LIST OF STATE STANDARDS

	STANDARD NO.	DESCRIPTION
	701400-03	APPROACH TO LANE CLOSURE, FREEWAY/ EXPRESSWAY
	701401-05	LANE CLOSURE, FREEWAY/ EXPRESSWAY
75	701411-05	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR FOR SPEEDS \geq 45 MPH
	701426-03	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION FOR SPEEDS ≥ 45 MPH
	701901-01	TRAFFIC CONTROL DEVICES
	704001-05	TEMPORARY CONCRETE BARRIER

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE RESIDENT ENGINEER SHALL CONTACT CORA MATHIS AREA TRAFFIC FIELD ENGINEER AT (847) 485-6475 A MINIMUM OF 2 WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKING.

ALL DAMAGES TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT NO ADDITIONAL COST TO THE DEPARTMENT

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT 847-705-4151 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM BRIDGE INSPECTORS

DO NOT SCALE PLAN FOR CONSTRUCTION DIMENSIONS

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE-NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE BID FOR THE WORK.

REINFORCEMENT BARS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A 706, GR 60 (IL MODIFIED). SEE SPECIAL PROVISIONS.

JOINT OPENING SHALL BE ADJUSTED ACCORDING TO ARTICLE 520.04 OF THE STD. SPECS. WHEN THE DECK IS POURED AT AN AMBIENT TEMPERATURE OTHER THAN 50°F

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINNG RESIDENTIAL AREAS

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

CONCRETE SUPERSTRUCTURE SHALL HAVE SEVEN DAY MINIMUM CURE

	Table 1979 He
	c:\projects\d120207\design_oo.dgn
-	

USER NAME = midyje DESIGNED - REVISED - DRAWN - REVISED -	
DRAWN - BEVISED	
DUANN - KEATSED -	
PLOT SCALE = 50.0000 '/ IN. CHECKED - REVISED -	
PLOT DATE = 10/30/2008 DATE - REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INDEX	OF SHEETS,	STATE	STANDA	ARDS &	GENERAL	NOTES
	SHEET NO.	OF	SHEETS	STA.	то	STA.

F.A.I SECTION					COUNTY	TOTAL SHEETS	SHEET NO.		
80		99-1-B-I-2				WILL	21	2	
						Т	CONTRACT	NO. 6	30D66
FED.	ROAD	DIST.	NO.	ILLINOIS	FED.	AID	PROJECT		