F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2008-067 BR	COOK	10	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

* FAP 351 & FAI 294

CONTRACT NO. 60F56

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	US 6 URBAN LOC. 1 SN 016-0383 STATE 100% SFTY-2A	I-80 URBAN LOC. 2 SN 016-2122 STATE 100% SFTY-2A	CONSTRUCTION TYPE CODE			
50157300	PROTECTIVE SHIELD	SQ YD	2368	2368					
50300225	CONCRETE STRUCTURES	CU YD	11.1		11.1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	4	1				
67100100	MOBILIZATION	L SUM	1	.7	.3				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
X0320887	POLYMER CONCRETE	CU FT	0.9	0.9					
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48					
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	94	94					
X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	188	188					
~~X0326305~~	~~STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)~~	~~SQ FT~~	~~338~~		~~338~~				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.7	0.3				
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	21	21					
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	217	217					
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1		1				
50102400	CONCRETE REMOVAL	CU YD	11		11				
X0321781	MECHANICAL SPLICE	EACH	20		20				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3420		3420				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	125		125				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	125		125				
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1		1				

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 10/29/2008

10/29/2008
c:\projects\8d\1305\design_cad\sm