F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	98-00153-02-BR	DUPAGE	65	11
STA. 101+25.00		TO STA. 114+00.00		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 63077

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER) — UNIT

STATION	OFFSET	UNIT
104+73.69	52.02RT	7
108+28.89	46.56LT	12
108+68.25	50.53LT	12
	TOTAL QUANTITY:	31

20101000 TEMPORARY FENCE — FOOT

STATION	OFFSET	STATION	OFFSET		UNIT
105+98.00	57.00	106+75.00	57.00	LT	90
107+90.00	57.00	109+85.00	45.00	LT	195
109+85.00	45.00	110+92.00	45.00	LT	107
105+32.00	62.00	105+51.00	58.00	RT	19
105+51.00	58.00	106+42.00	60.00	RT	91
107+72.00	55.00	108+42.00	52.00	RT	70
108+42.00	52.00	111+80.00	46.00	RT	338
111+80.00	42.00	112+98.00	42.00	RT	118
112+98.00	42.00	114+00.00	49.00	RT	102
				TOTAL QUANTITY:	1,130

20700420 POROUS GRANULAR EMBANKMENT, SUBGRADE — CU YD

STATION	WIDTH (FT)	STATION	WIDTH (FT)	DEPTH (INCH)	UNIT
110+50.00	67.0	- 112+00.00	67.0	6"	186
				TOTAL QUANTITY:	186

20800150 TRENCH BACKFILL — CU YD

STATION	OFFSET		PIPE LENGTH	CU YDS/FT	UNIT
105+00.00	30.0	LT	100	0.132	13.20
104+00.00	30.6	LT	12	0.132	1.56
110+68.00	30.0	LT	38	0.132	5.02
111+06.00	30.0	LT	38	0.132	5.02
111+85.00	30.0	LT	79	0.132	10.43
102+75.00	32.0	RT	25	0.132	3.30
104+00.00	30.6	RT	100	0.194	19.40
105+00.00	30.0	RT	100	0.278	27.80
109+25.00	30.0	RT	53	0.132	7.00
109+78.00	30.0	RT	52	0.132	6.86
110+30.00	31.0	RT	38	0.132	5.02
111+06.00	30.0	RT	38	0.132	5.02
111+85.00	30.0	RT	79	0.132	10.43
109+15.00	30.0	LT	16	0.213	3.41
109+78.00	30.0	LT	63	0.143	9.01
110+30.00	30.0	LT	52	0.121	6.29
103+00.00	32.0	RT	11	0.121	1.33
110+68.00	30.0	RT	16	0.121	1.94
101+40.00	25.1	RT	15	0.647	9.71
				TOTAL QUANTITY:	152

25001820 SEEDING, CLASS 5 (MODIFIED) — ACRE

STATION	OFFSET		STATION	OFFSET	UNIT
101+25	RT	-	106+42	RT	0.32
107+69	RT	-	114+00	RT	0.19
101+25	LT	-	103+18	LT	0.03
103+18	LT	-	106+66	LT	0.13
107+92	LT		114+00	LT	0.16
				TOTAL I000-2A:	0.83
				TOTAL QUANTITY:	0.83

25002014 SEEDING, CLASS 4A (MODIFIED) — ACRE

STATION	OFFSET		STATION	OFFSET	UNIT
101+25	RT	-	106+42	RT	0.32
107+69	RT	-	114+00	RT	0.19
101+25	LT	-	103+18	LT	0.03
103+18	LT	-	106+66	LT	0.13
107+92	LT		114+00	LT	0.16
				TOTAL I000-2A:	0.83
				TOTAL QUANTITY:	0.83

25100630 EROSION CONTROL BLANKET — SQ YD

STATION	OFFSET		STATION	OFFSET	UNIT
101+25	RT	-	106+42	RT	3,076
107+69	RT	-	114+00	RT	1,873
101+25	LT	-	103+18	LT	283
103+18	LT	-	106+66	LT	1,295
107+92	LT		114+00	LT	1,556
				TOTAL I000-2A:	8,082

28100105 STONE RIPRAP, CLASS A3 — SQ YD

STATION	OFFSET		UNIT
100+60	RT		5
		NON PARTICIPATING:	5
103+00	RT		5
104+00	LT		5
104+50	RT		30
106+65	RT		10
109+25	LT		5
110+68	RT		5
		TOTAL I000-2A:	60

35101800 AGGREGATE BASE COURSE, TYPE B, 6" — SQ YD

STATION	WIDTH		STATION	WIDTH	UNIT
102+00.00 LT	34.5	-	103+48.45 L	34	284
				TOTAL QUANTITY:	284

40600200 BITUMINOUS MATERIALS (PRIME COAT) — TON

STATION	WIDTH (FT)		STATION	WIDTH (FT)	UNIT
AT APPLICATION RATE OF 0.0004 TONS/SQ YD					
101+25.00	64	-	106+23.17	60	5.5
108+11.83	60	-	112+00.00	60	4.1
112+00.00	60	-	114+00.00	70	1.3
				TOTAL QUANTITY:	11.0

40600300 AGGREGATE (PRIME COAT) — TON

STATION	WIDTH (FT)	STATION	WIDTH (FT)	UNIT
AT APPLICATION RATE OF 0.002 TONS/SQ YD				
101+25.00	64	- 106+23.17	60	19
108+11.83	60	- 112+00.00	60	21
112+00.00	60	- 114+00.00	70	7
			TOTAL QUANTITY:	47

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / R.O.W. CHECKED / R.O.W. NOTED / STRUCTURE NOTATNG CHKD — NOTE BOOK NO. ____ — FILE NAME — BY — DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / R.O.W. NOTED / STRUCTURE NOTATNG CHKD — NOTE BOOK NO. ____ — BY — DATE

PLOT DATE = 11/5/2008
FILE NAME = $FILE$
PLOT SCALE = $SCALE$
USER NAME = $USER$

$$DGN$$
$$PRF$$

GRAPHIC SCALE IN FEET
100 50 0 50 100

PB PARSONS BRINCKERHOFF

REVISIONS	
NAME	DATE
M. SHAH	11/06/08

DUPAGE COUNTY DIVISION OF TRANSPORTATION
THORNDALE AVENUE OVER SALT CREEK

SCHEDULE OF QUANTITIES

SCALE:
DATE 09-05-08
DRAWN BY MS
CHECKED BY RH