SUMMARY OF QUANTITIES

SPECIALTY ITEM	ITEM	DESCRIPTION	UNIT	HPP QUANTITY	STP QUANTITY	CMAQ		Y047 TOTAL QUANTITY
						(1) ELM QUANTITY	(2) 88TH QUANTITY	
	20100110	TREE REMOVAL (6-15 UNITS DIAMETER)	UNIT	36	0	0	0	36
	20101000	TEMPORARY FENCE	FOOT	200	0	0	0	200
*	20101200	TREE ROOT PRUNING	EACH	55	0	0	0	55
	20200100	EARTH EXCAVATION	CU YD	187	0	51	854	1092
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	435	0	76	332	843
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	827	0	64	27	918
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	7700	0	495	1375	9570
	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	0	385	36	215	636
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	0	185	10	30	225
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	0	185	10	30	225
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	0	185	10	30	225
*	25100630	EROSION CONTROL BLANKET	SQ YD	0	216	0	0	216
	28000400	PERIMETER EROSION BARRIER	FOOT	8060	0	425	1400	9885
	28100107	STONE RIPRAP, CLASS A4	SQ YD	0	70	0	0	70
	28200200	FILTER FABRIC	SQ YD	0	20	0	0	20
	35102100	AGGREGATE BASE COURSE, TYPE B, 9"	SQ YD	7700	0	495	1375	9570
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50	TON	1461	0	94	273	1828
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	0	220	170	120	510
	44000100	PAVEMENT REMOVAL	SQ YD	7700	0	0	0	7700
	44000600	SIDEWALK REMOVAL	SQ FT	0	220	170	120	510
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	0	0	0	1
	50200100	STRUCTURE EXCAVATION	CU YD	38	0	0	0	38
	50300225	CONCRETE STRUCTURES	CU YD	13.3	0	0	0	13.3
	50800105	REINFORCEMENT BARS	POUND	1560	0	0	0	1560
	51200956	FURNISHING METAL SHELL PILES 12"x0.179"	FOOT	120	0	0	0	120
	51202305	DRIVING PILES	FOOT	120	0	0	0	120
	54200427	PIPE CULVERTS, TYPE 1, RCCP 12"	FOOT	95	0	0	0	95
	54200430	PIPE CULVERTS, TYPE 1, RCCP 15"	FOOT	5	0	0	0	5
	54213657	PRC FLARED END SECTIONS 12"	EACH	4	0	0	0	4
	54213660	PRC FLARED END SECTIONS 15"	EACH	1	0	0	0	1
	60403800	LIDS, TYPE 1, CLOSED LID	EACH	1	0	0	0	1
	67100100	MOBILIZATION	L. SUM	0	0.5	0.25	0.25	1
	70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	0	0.5	0.25	0.25	1
	70102620	TRAFFIC CONTROL AND PROTECTION - 701501	L. SUM	0	0.5	0.25	0.25	1
	70102635	TRAFFIC CONTROL AND PROTECTION - 701701	L. SUM	0	0.5	0.25	0.25	1
	70102640	TRAFFIC CONTROL AND PROTECTION - 701801	L. SUM	0	0.5	0.25	0.25	1
	72000100	SIGN PANEL TYPE 1	SQ FT	0	0	2.25	2.25	4.5
	72900100	METAL POST TYPE A	FOOT	0	0	12	12	24
*	78000200	THERMOPLASTIC PAVEMENT MARKING LINE, 4"	FOOT	0	7715	435	1400	9550
	X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	0	167	112	76	355
	Z0013798	CONSTRUCTION LAYOUT	L. SUM	0	0.5	0.25	0.25	1
*	X0322508	PEDESTRIAN TRUSS SUPERSTRUCTURE	SQ FT	304	0	0	0	304
	XX007750	GROUTED STONE RIPRAP, CLASS A4	SQ YD	20	0	0	0	20
*	25001100	SEEDING, CLASS 3 (SPECIAL)	ACRE	0	1.95	0.1	0.35	2.4
*	XX007751	LYTHRUM ALATUM (WINGED LOOSESTRIFE) NATIVE FORB PLUGS	EACH	0	494	0	0	494
	XX007752	CONCRETE RETAINING WALL	FOOT	520	0	0	0	520

* INDICATES SPECIALITY ITEM