

SUMMARY OF QUANTITIES						
CODE NO	ITEM	UNIT	TOTAL QUANTITY 80% FED. 20% STATE	CONSTR. TYPE CODE		
				ROADWAY 1000	SN 050-2051 Y007	SN 050-2052 X028-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	52	52		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	42	42		
20200100	EARTH EXCAVATION	CU YD	538	538		
20400800	FURNISHED EXCAVATION	CU YD	974	974		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1810	1810		
25000300	SEEDING, CLASS 3	ACRE	1	1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	78	78		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	78	78		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	78	78		
25100630	EROSION CONTROL BLANKET	SQ YD	4164	4164		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	258	258		
28000300	TEMPORARY DITCH CHECKS	EACH	16	16		
28000400	PERIMETER EROSION BARRIER	FOOT	160	160		
28100107	STONE RIPRAP, CLASS A4	SQ YD	195	23	57	115
28200200	FILTER FABRIC	SQ YD	195	23	57	115
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	739	739		
35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SQ YD	467	467		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	427	427		
40600300	AGGREGATE (PRIME COAT)	TON	11	11		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	247	247		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	640	640		
40600990	TEMPORARY RAMP	SQ YD	27	27		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	494	494		
44000100	PAVEMENT REMOVAL	SQ YD	467	467		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	52	52		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1705	1705		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1
50105200	REMOVE EXISTING CULVERTS	EACH	2	2		
50500505	STUD SHEAR CONNECTORS	EACH	74			74
50800105	REINFORCEMENT BARS	POUND	45590		12700	32890
51500100	NAME PLATES	EACH	2		1	1
54003000	CONCRETE BOX CULVERTS	CU YD	255		84	171
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1254	1254		
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	5	5		
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	3	3		
63200310	GUARDRAIL REMOVAL	FOOT	1492	1492		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		

• SPECIALTY ITEMS

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	TOTAL QUANTITY 80% FED. 20% STATE	CONSTR TYPE CODE		
				ROADWAY 1000	SN 050-2051 Y007	SN 050-2052 X028-2A
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	217	217		
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	2736	2736		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	542	542		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	73	73		
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2736	2736		
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	542	542		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	35	35		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	35	35		
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	772			772
X7011005	TRAFFIC CONTROL AND PROTECTION OFR TEMPORARY DETOUR	L SUM	1	1		

• SPECIALTY ITEMS

FILE NAME =	USER NAME = breboygo	DESIGNED - ---	REVISED - ---
o:\pw\work\pwwd\breboygo\dms40744\0368635 Details.DGN		DRAWN - ---	REVISED - ---
	PLOT SCALE = 50.0092' / IN.	CHECKED - ---	REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
587	(22)I & I-1	LASALLE	31	3
CONTRACT NO. 66975				