

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE										
CODE NO	ITEM	UNIT		ROADWAY 1000-2A 80% FEDERAL 20% STATE	STRUCTURE X371-5B 80% FEDERAL 20% STATE	ROADWAY 1000-2A 100% COUNTY	SIGNALS Y031-1F 80% FEDERAL 20% STATE	LIGHTING Y030-1E 80% FEDERAL 20% STATE						
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, No.18 3 PAIR	FOOT	1707.5				1707.5							
87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	2				2							
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55FT.	EACH	2				2							
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5				3.5							
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	56				56							
87900200	DRILL EXISTING HANDHOLE	EACH	2				1	1						
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAS T-ARM MOUNTED	EACH	7				7							
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRA CKET MOUNTED	EACH	1				1							
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAS T ARM MOUNTED	EACH	4				4							
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRA CKET MOUNTED	EACH	6				6							
88200310	TRAFFIC SIGNAL BACKPLATE, LOUVERED, PLAS TIC	EACH	11				11							
88500100	INDUCTIVE LOOP DETECTOR	EACH	12				12							
88600100	DETECTOR LOOP, TYPE I	FOOT	1546				1546							
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1				1							
89502380	REMOVE EXISTING HANDHOLE	EACH	10				10							
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5				5							
Z0017202	DOWEL BARS 1 1/2"	EACH	2660	2660										
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIR ECTIVE), TEST LEVEL 3	EACH	1	1										
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY RED IRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1										
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1										
⚠														
XX004093	CONCRETE SLOPEWALL REMOVAL	50 FT	7920	7920										
XX005703	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT . SPECIAL	L SUM	1				1							
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	591.4	591.4										
X0321583	PIPE ELBOW 18"	EACH	2	2										
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	6	6										
⚠														
REVIS														
12/19/08														
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES										
F.A.U. RTE. 6758				SECTION (1-R),(1-VC)BR				COUNTY PEORIA				TOTAL SHEETS 142		
FED. ROAD DIST. NO.				ILLINOIS FED. AID PROJECT										